NOTICE TO THE AUDIENCE: Please remember that if you are interested in matters on the agenda that will have subsequent meetings, it is your responsibility to note their dates, times, and places. No further letters or reminders will be sent. Of course, if you have any questions about any given matter, do not hesitate to contact the Planning Department in the City Hall Annex, 4403 Devils Glen Road, Bettendorf, lowa 52722 or phone (563) 344–4100. The Planning and Zoning Commission meeting will be open to the public. The City of Bettendorf will broadcast this public meeting online at http://www.bettendorf.org/live-meeting.

PLANNING AND ZONING COMMISSION CITY OF BETTENDORF APRIL 16, 2025 AT 5:30 PM CITY HALL COUNCIL CHAMBERS 1609 STATE STREET

1.	Roll Call: Gibson, Kappeler, Ormsby, Satterfield	
	Scaife, Stoltenberg, Wennlund	
2.	Approval of the minutes of the meeting of March 19, 2025.	
3.	Review of Commission procedures.	

Public Hearing

- 4. <u>Case 25-0016-REZ; Rezone from A-1 to R-2, submitted by Windmiller Development, Pleasant Valley Community School District, and Forest Grove School Preservation.</u> (Staff: Beswick)
- 5. <u>Case 25-017-REZ; Rezone from A-1 to C-3, submitted by Windmiller Development.</u> (Staff: Beswick)
- 6. <u>Case 25-018-ORD</u>; Amendments to Title 11, Chapter 4 Permitted Use Table, to allow Convenience Storage in the C-3 District as a Special Use, submitted by the City of Bettendorf. (Staff: Beswick)

Preliminary Plat

- 7. <u>Case 25-019-PP; Preliminary Plat of Blackstone addition, a single-family residential subdivision, submitted by Windmiller Development.</u> (Staff: Beswick)
- 8. <u>Case 25-013-PP; Preliminary Plat of Ridgehaven Subdivision, a single-family residential subdivision, submitted by Pheasant Creek Estates, LLC.</u> (Staff: Beswick)

Site Development Plan

8. <u>Case 25-015-SDP; Site Development Plan for four multifamily buildings located on Lot 2, Crowne Pointe Fourth Addition and Lot 2, Crowne Pointe Seventh Addition, submitted by Everest Homes, LLC.</u> (Staff: Beck)

Other

- 8. 2025 Zoning Ordinance Update:
 - o Cont'd Chapter 4. Permitted Use Table.
 - o Chapter 5. Site Development Regulations.
- 9. Commission Update.



The materials for the Planning and Zoning Commission meeting can be accessed by scanning the QR code.

NOTICE TO THE AUDIENCE: Please remember that if you are interested in matters on the agenda that will have subsequent meetings, it is your responsibility to note their dates, times, and places. No further letters or reminders will be sent. Of course, if you have any questions about any given matter, do not hesitate tocontact the Planning Department in the City Hall Annex, 4403 Devils Glen Road, Bettendorf, lowa 52722 or phone (563) 344-4100.

MINUTES PLANNING & ZONING COMMISSION MARCH 19, 2025 5:30 P.M.

The Planning & Zoning Commission meeting of March 19, 2025 was called to order by Stoltenberg at 5:30 p.m. in the City Hall Council Chambers, 1609 State Street.

1. Roll Call

MEMBERS PRESENT: Gibson, Kappeler, Scaife, Stoltenberg, Wennlund

MEMBERS ABSENT: Ormsby, Satterfield

STAFF PRESENT: Taylor Beswick, Senior City Planner; Greg Beck, City Planner; Mark Hunt,

Community Development Director; Chris Curran, City Attorney; Troy

Said, Fire Chief; Lisa Fuhrman, Secretary

2. Approval of the minutes of the meeting of February 19, 2025.

On motion by Kappeler, seconded by Wennlund, that the minutes of the meeting of February 19, 2025 be approved as submitted.

ALL AYES

Motion carried.

3. Review of Board procedures.

Stoltenberg introduced Guy Scaife, the newly-appointed Commissioner.

Election of officers.

On motion by Kappeler, seconded by Scaife, that Wennlund continue to serve as Chair for 2025.

Motion carried.

<u>Replat</u>

5. <u>Case 25-012-REPL; Spencer Hollow 6th Addition (Replat of Lot B in Spencer Hollow 4th Addition)</u>, submitted by Ven Green Land Development, LLC. (Staff: Beck)

Beck reviewed the staff report.

Scaife asked if the proposed plat is consistent with previous additions. Beck confirmed this. Hunt added that because the right-of-way width in the previous additions is 52 feet, the right-of-way in the proposed subdivision will be the same rather the currently required 53 feet.

Wennlund asked if the detention outlot is part of a previous subdivision. Beck confirmed this.

On motion by Kappeler, seconded by Wennlund, that the final plat of Spencer Hollow 6th Addition be recommended for approval subject to staff recommendations.

ROLL CALL ON MOTION

ALL AYES

Motion carried.

- 6. <u>Case 25-005-FP; Blackbird Heights Addition (Replat of Lot 1 in Highland Ridge Third Addition)</u>, submitted by G2 Partners, LLC. (Staff: Beswick)
- 7. <u>Case 25-006-FP; Gipple's Second Addition (Replat of Gipple's First Addition and Lots 4 and A I Blackbird Heights Addition)</u>, submitted by Todd Gipple. (Staff: Beswick)

Beswick reviewed the staff report.

Kappeler asked if there is any construction activity currently underway. Beswick explained that there is grading going on in an adjacent subdivision in anticipation of the installation of the extension of Cardinal Road and stated that neither of the proposed subdivisions include dedication of right-of-way. He indicated that home construction is taking place only in previously platted subdivisions.

Kappeler asked if anything would be allowed to be constructed on Lot 1A of Gipple's Second Addition. Beswick explained that it would contain the storm water detention infrastructure for Gipple's Second Addition, adding that no development is allowed to occur on outlots. Hunt added that there will be fewer lots in the area currently being platted than were originally anticipated during an earlier platting stage.

March 19, 2025

On motion by Kappeler, seconded by Wennlund, that the final plat of Blackbird Heights Addition be recommended for approval subject to staff recommendations.

ROLL CALL ON MOTION

ALL AYES

Motion carried.

Beswick reviewed the staff report.

On motion by Kappeler, seconded by Wennlund, that the final plat of Gipple's Second Addition be recommended for approval subject to staff recommendations.

ROLL CALL ON MOTION

ALL AYES

Motion carried.

<u>Public Hearing</u>

8. <u>Case 25-004-ORD; Amendment to Title 11, Chapter 14 of the City Code - Sign Ordinance.</u> (Staff: Beswick)

Beswick reviewed the proposed amendment to Section 11-4-3(F) regarding public service and safety signs.

A brief discussion was held regarding the possibility of utilizing the banners at some point in the future to promote events taking place in the city, to acknowledge awareness weeks, or to celebrate local sports achievements.

Kappeler asked how the proposed banners are different than those that are displayed in the downtown area. Curran explained that they are not different, adding that staff's goal is to amend the code so that it is consistent with the present reality downtown and to add the TBK area as a permitted location as well as the sponsorship component of the banner. Beswick added that the ordinance also adds new sign types for public safety, legal notice, and public utility signs.

Stoltenberg asked if there is a means to limit the number, location, and separation distance for the signs. Curran explained that there will be an administrative policy which will regulate the types of poles on which the banners are allowed, limit the number and type of signs allowed in the right-of-way, and ensure that the signs are aesthetically-pleasing. He reiterated that the signs are only to be allowed on city-owned poles, adding that the city or an authorized vendor will be responsible for the maintenance of the signs.

Beswick reviewed the proposed amendment to Section 11-4-8(B) regarding billboard signs.

Wennlund asked if there are any existing billboards in the I-80 Urban Renewal Area that would become non-conforming. Beswick confirmed that there are some in the agricultural fields north of I-80, adding that they would not be required to be removed but would become legal non-conforming signs. Hunt commented that the area is becoming a major entry point into the city because of the upcoming I-80 interchange construction and the growth in the TBK area. He added that the city has given a lot of consideration to the first impression the area makes and that one of the top priorities is to prohibit billboards in the overlay district.

Kappeler asked if the existing billboards in the area would be eligible for conversion to a digital sign. Curran explained that once the ordinance is adopted, the non-conforming signs would not be allowed to be changed.

Stoltenberg opened the public hearing for Case 25-004-ORD and asked if there is proof of publication. Fuhrman confirmed this.

There being no one present wishing to speak in favor of or in opposition to the ordinance amendment, Stoltenberg closed the public hearing.

On motion by Kappeler, seconded by Wennlund, that the ordinance amending Sections 11-4-3(F) and 11-4-8(B) of Title 11, Chapter 14 of the City Code – Sign Ordinance be recommended for approval subject to staff recommendations.

AYE: Gibson, Kappeler, Scaife, Stoltenberg, Wennlund

NAY: None

ALL AYES

Motion carried.

Other

Zoning Ordinance Update: Continued discussion of proposed Chapter 4: Zoning Districts and Permitted Use Table. Staff and Commissioners discussed commercial and industrial districts and considerations for changes to these districts in the code update.

There being no further business, the meeting adjourned at approximately 7:00 p.m.

STAFF REPORT

Subject: Planning and Zoning Commission

Author: Taylor Beswick

Department: Community Development

Date: April 11, 2025



Case Nos.: 25-016-REZ & 25-017-REZ

Request: Rezone from A-1 to R-2 (93.4 acres) and A-1 to C-3 (16.84 acres) (total of 111.8 acres)

Location: North of Forest Grove Drive, west of Wells Ferry Road, and south of I-80

Applicants: Windmiller Development, Pleasant Valley Community School District, and Forest

Grove School House Preservation

Current Zoning: A-1, Agricultural/Urban Reserve District

Proposed Zoning: R-2, Single-Family Residence District & C-3, General Business

Future Land Use: A mixture of CC, Community Commercial; NL, Neighborhood Light; P, Public; GW,

Greenways; and Open Space

Related Cases: 23-020-ANNEX Wells Ferry Road/Forest Grove Drive Annexation; 25-019-PP Blackstone

Addition Preliminary Plat; 25-018-ORD Permitted Use Table, Commercial Uses

Background Information & Facts

Windmiller Development, Pleasant Valley Community School District, and Forest Grove School House Preservation has submitted a request to rezone approximately 94.34 acres of land located north of Forest Grove Drive, west of Wells Ferry Road, and south of I-80 from A-1 to R-2 (see Aerial Map - Attachment A). In addition, Windmiller Development has submitted a request to rezone approximately 16.84 acres of land in the same area from A-1 to C-3. Property contained within the rezoning area is currently farmland, except for the Forest Grove School House, and was recently annexed into the City of Bettendorf. Proposed uses of the entire area include an 88-lot, single-family subdivision, a future Pleasant Valley Community School District school, the existing Forest Grove School House (a historic structure), and indoor commercial storage units.

The annexation was conducted during the most recent Comprehensive Plan update; thus the Future Land Use Map aligns with the proposed developments on the property. In addition, Spencer Creek runs through the property resulting in portions being designated as Parks & Open Space. Upon successful annexation into the City of Bettendorf, property is automatically zoned A-1. The proposed R-2 and C-3 zoning are compliant with the proposed uses, pending the consideration of Case No. 25-018-ORD which will allow convenience storage in the C-3 District via a Special Use Permit approved by the Board of Adjustment. A-1 zoning is also present to the east. Single-family developments exist to the north and south of this parcel (see Future Land Use and Current Zoning – Attachment B; Proposed Zoning – Attachment C).

A submitted concept plan shows the proposed configuration of these lots (see Annexation Concept – Attachment D). Windmiller Development has also submitted the Preliminary Plat of Blackstone Addition, the residential portion of this rezoning (see Case No. 25-019-PP). Portions of the property are in Special

Flood Hazard Areas, and the applicant's development team has taken this fact into account for siting on the rezoning tract and future single-family lots or commercial lots.

Future Land Use and Comprehensive Plan

As noted previously, the Future Land Use Map designates the area of the rezoning as multiple future land use categories. The proposed zoning and proposed uses are compatible and consistent with the Comprehensive Plan.

Multiple Comprehensive Plan goals are met by the proposed development including preserving environmental sensitive areas, implementing the annexation 7-point strategies, and enhancing community character with improved education services making Bettendorf a great place to live.

Zoning Compliance

The residential rezoning tract is intended to be subdivided single-family lots, a future school, and a historic schoolhouse which are permitted in the R-2 district. The northern commercial zoning tract is proposed to be indoor storage, which requires a Zoning Ordinance Text Amendment (see Case No. 25-018-ORD). The rezoning tract is of sufficient size for the proposed uses and is located in an area that can be developed. All additional bulk standards and regulations have been sufficiently considered for the rezoning including floor area, height, and setbacks.

Rezoning requests must adequately address the following concerns as outlined in Section 11-15-13(B). Staff has addressed each requirement:

- 1. The rezoning conforms to the future land use map in the comprehensive plan, as described in the Preamble and further in subsection A-1-3 of Appendix 1. Yes, as described in the "Future Land Use and Comprehensive Plan" section of this report.
- 2. The amendment is consistent with the goals and objectives of the comprehensive plan. Yes, as described in the "Future Land Use and Comprehensive Plan" section of this report.
- 3. The subject property, after the city council approval of the requested rezoning, will be designed so as to permit characteristics of said zoning district that will not negatively impact the nearby parcels. The proposed single-family residential use is a desirable and attractive development at this location, and staff contends it will not negatively impact nearby parcels. Staff contends the proposed commercial zoning area is naturally buffered from surrounding uses which isolate any potential negative impacts that could be present, depending on the commercial use.
- 4. The potential externalities and applicable performance standards requirements governing factors (such as noise, neon lights, odors, etc.) of the rezoning request have been adequately considered. No potential negative externalities have been identified for the proposed residential use. Additional site plan reviews will be required to analyze impacts of any proposed school/public uses and commercial uses.
- 5. There are adequate public utilities and services available to the land if rezoned. If not, there is an identified party who will pay to install them. Forest Grove Drive is public right-of-way and adjacent to the proposed rezoning tract, and further access is described in the "Thoroughfare Plan & Access" section of this report. Connection to utilities, sanitary sewer, and stormwater detention are feasible given the

location and size of the proposed rezoning tract. A more detailed analysis and review of these connections and requirements will be conducted at the platting stage.

- 6. The pattern of development that has occurred surrounding the subject property is examined, as other characteristics of the subject property are considered, to make a determination regarding a request for an amendment change. A R-2 Zoning District is an appropriate district for this location and is consistent with the pattern of development occurring west of this area in Sterling Woods Subdivision and the Spencer Hollow Subdivisions. A commercial development which is bound by Spencer Creek, I-80, and Wells Ferry Road is appropriate given the limited access and sufficient natural buffers present.
- 7. The proposed amendment is in the public interest and not solely in the interests of the applicant. The amendment is in the public interest due to goal consistencies described in the section "Future Land Use and Comprehensive Plan" of this report.

Thoroughfare Plan & Access

Forest Grove Drive and Wells Ferry Road will provide access to future developments within the rezoning area. As part of the residential subdivision, local public streets will connect to existing roads west of the Forest Grove School House on Forest Grove Drive and north of the Pleasant Valley Community School District property on Wells Ferry Road. The future Pleasant Valley Community School building will have curb cuts onto Wells Ferry Road and Forest Grove Drive while the existing access for the Forest Grove School House will remain on Forest Grove Drive. Further analysis and review will be conducted during the platting stage and/or site development plan stage.

Utilities and Services

All new developments within the rezoning tract will be served by the Spencer Creek sanitary sewer lift station, currently under construction. Iowa American Water and MidAmerican Energy have capacity to extend water, gas, and electric to future developments in the area.

Other Platting Considerations

Staff contends the submitted rezoning exhibit and additional information addresses all relevant information for reviewing the rezoning request. Further details will be provided, analyzed, and reviewed at the platting stage and or site development plan stage for proposed uses within the rezoning area.

Staff Recommendation

Given the evidence and reasons stated in the staff analysis of the request, staff recommends the Planning and Zoning Commission recommend <u>approval</u> of the proposed rezoning requests:

- Case No. 25-016-REZ: A-1 to R-2
- Case No. 25-017-REZ: A-1 to C-3

Taylor Beswick, Senior City Planner


Attachments:

<u>Aerial Map - Attachment A; Future Land Use and Current Zoning - Attachment B; Proposed Zoning - Attachment C; Annexation Concept - Attachment D</u>




Case No. 25-016-REZ & 25-017-REZ Rezone: A-1 to R-2 and A-1 to C-3 Aerial - Attachment A

1 Inch = 1,333 Feet 500 1,000 2,000 3,000







Case No. 25-016-REZ & 25-017-REZ Rezone: A-1 to R-2 and A-1 to C-3 Future Land Use & Zoning - Attachment B










REZONING EXHIBIT

WINDMILLER FOREST GROVE BETTENDORF, IOWA

PROJECT LOCATION MAP:



(NOT TO SCALE)

APPLICANT INFORMATION:

APPLICANT/OWNER: WINDMILLER DEVELOPMENT, LLC

P.O. BOX 790 BETTENDORF, IA 52722

PREPARED BY:

AXIOM CONSULTANTS, LLC C/O BRIAN BOELK 300 S. CLINTON STREET, UNIT 200 IOWA CITY, IOWA 52240 319-519-6220 BBOELK@AXIOM-CON.COM

LEGAL DESCRIPTION:

ZONED TO C-3:

BEING THE NORTHERN PORTION OF CORRECTED AUDITOR'S PARCEL A AS RECORDED IN 2024-5174 OF THE SCOTT COUNTY RECORDER'S OFFICE DESCRIBED AS:

BEGINNING AT THE NORTHWEST CORNER OF SAID CORRECTED AUDITOR'S PARCEL A; THENCE N87°43'35"E, 662.59 FEET; THENCE S81°51'18"E, 189.70 FEET; THENCE N86°32'59"E, 940.47; THENCE S20°07'51"E, 425.71 FEET; THENCE S78°05'05"W, 853.49 FEET; THENCE N70°28'47"W, 1161.59 FEET; THENCE N02°15'48"W, 131.87 FEET TO THE POINT OF BEGINNING.

ALL IN THE CITY OF BETTENDORF, SCOTT COUNTY, IOWA. DESCRIBED AREA CONTAINS 16.84 ACRES AND IS SUBJECT TO EASEMENTS AND OTHER RESTRICTIONS OF RECORD.

ZONED TO R-2:

BEING PART OF CORRECTED AUDITOR'S PARCEL A AS RECORDED IN 2024-5174, ALL OF AUDITOR'S PARCEL B AS RECORDED IN 2024-5420, AND ALL OF THE LEASE PARCEL AS RECORDED IN 2022-24374 OF THE SCOTT COUNTY RECORDER'S OFFICE, CITY OF BETTENDORF, SCOTT COUNTY, IOWA, EXCEPT THE NORTHERN PORTION OF SAID CORRECTED AUDITOR'S PARCEL A DESCRIBED AS:

BEGINNING AT THE NORTHWEST CORNER OF SAID CORRECTED AUDITOR'S PARCEL A; THENCE N87°43'35"E, 662.59 FEET; THENCE S81°51'18"E, 189.70 FEET; THENCE N86°32'59"E, 940.47; THENCE S20°07'51"E, 425.71 FEET; THENCE S78°05'05"W, 853.49 FEET; THENCE N70°28'47"W, 1161.59 FEET; THENCE N02°15'48"W, 131.87 FEET TO THE POINT OF BEGINNING.

ALL IN THE CITY OF BETTENDORF, SCOTT COUNTY, IOWA. DESCRIBED AREA CONTAINS 94.34 ACRES AND IS SUBJECT TO EASEMENTS AND OTHER RESTRICTIONS OF RECORD.

ZONING INFORMATION:


CURRENT ZONING:


A-1 AGRICULTURAL/URBAN RESERVE DISTRICT

PROPOSED ZONING:

C-3 GENERAL BUSINESS DISTRICT

R-2 SINGLE-FAMILY RESIDENCE DISTRICT





B


ISSUED FOR REVISED SUBMITTAL

DATE 03-05-2025 DESCRIPTION DATE

PROJECT NO. 22-0199

REZONING EXHIBIT

1 OF 1



Staff Report

Subject: Planning & Zoning Commission

Author: Taylor Beswick

Department: Community Development

Date: April 11, 2025

Case No.: 25-018-ORD

Request: Amend sections of 11-4-5(B.): Commercial And Parking Permitted Use Table

Location: City-wide in the C-3, General Business District

Applicant: Community Development Staff

Summary: Amends Zoning Ordinance Permitted Use Table (11-4-5B) to allow convenience

storage in the C-3 District after approval of a Special Use Permit.

Background Information, Facts, and Staff Analysis

Staff is proposing to amend a section of Title 11: Chapter 4 Permitted Use Tables for the following purposes:

- To allow convenience storage in the C-3 District, subject to approval of a Special Use Permit by the Board of Adjustment.
- Convenience storage is only allowed in Industrial Districts.
- Convenience storage is defined as: "Storage services primarily for personal effects and household goods within enclosed storage areas having individual access but excluding use of such areas as workshops, hobby shops, manufacturing, or commercial activity."
- This will allow commercial in-fill in certain cases and not require the rezoning of property to industrial districts which could permit more impactful uses.

Attachment A contains the redline amendments to 11-4-5(B.). Development trends have shown demand for personal storage. Staff contends that there are instances where personal in-door storage or mini-warehousing can be compatible with surrounding uses in areas zoned C-3, General Commercial. Staff is not endorsing the use where there is a potential for commercial uses which provide jobs, services, or a more intensive commercial use based on criteria such as traffic, connectivity, and overall development factors. Given the criteria stated, a requirement for a Special Use Permit by the Board of Adjustment is recommended for a case-by-case analysis for permitting convenience storage in the C-3 District.

Staff Recommendation

Staff contends the proposed amendments enhance the City of Bettendorf's economic development tools and encourage redevelopment and investment in commercial areas, all goals outlined in the City's Comprehensive Plan. Staff recommends approval of Case 25-018-ORD, Zoning Ordinance amendments to section 11-4-5(B.)

Respectfully submitted, Taylor Beswick, Senior City Planner

25-018-ORD: Amendment to Permitted Use Table - Attachment A

Table 11-4-5B Commercial And Parking Permitted Use Table

RED = Amendment

"Convenience Storage Use Type"

Zoning Districts	A 1	A2	R1	R2	R3	R4	R5	RMHP	C1	C2	C3	C6	C7	I1	12	13	Supplemental Regulations
Use Types																	
Convenience											S			Р	Р	Р	stds in supp
Storage																	regs

STAFF REPORT

Subject: Planning and Zoning Commission

Author: Taylor Beswick

Department: Community Development

Date: April 11, 2025



Case Nos.: 25-019-PP

Request: Preliminary Plat Review of an 88-lot, single-family residential subdivision

Location: North of Forest Grove Drive, west of Wells Ferry Road, and south of I-80

Applicants: Windmiller Development

Current Zoning: A-1, Agricultural/Urban Reserve District

Proposed Zoning: R-2, Single-Family Residence District (Case No. 25-016-REZ); C-3, General Business

District (Case No. 25-017-REZ)

Future Land Use: Predominately NL, Neighborhood Light; some GW, Greenways; and OS, Open Space

Related Cases: 23-020-ANNEX Wells Ferry Road/Forest Grove Drive Annexation; 25-016-REZ A-1 to R-

2; 25-017-REZ A-1 to C-3; 25-018-ORD Allow Indoor Storage in C-3 with SUP

Background Information & Facts

Windmiller Development has submitted a request to review a Preliminary Plat of the Blackstone addition which includes 88 detached single family lots on 90.66 acres of land located north of Forest Grove Drive, west of Wells Ferry Road, and south of I-80 (see Aerial Map - Attachment A). Lot 51 of the Preliminary Plat encompasses an area currently be considered to be rezoned from A-1 to C-3. Property contained within the development area is currently farmland and adjacent land includes the Forest Grove School House and future Pleasant Valley Community School District development. A majority of the land in the Preliminary Plat was recently annexed into the City of Bettendorf.

The annexation was conducted during the most recent Comprehensive Plan update; thus the Future Land Use Map aligns with the proposed developments on the property. In addition, Spencer Creek runs through the property resulting is portions being designated as Parks & Open Space. Upon successful annexation into the City of Bettendorf, property is automatically zoned A-1. The proposed R-2 and C-3 zoning are compliant with the proposed uses, pending the consideration of Case No. 25-018-ORD which will allow convenience storage in the C-3 District via a Special Use Permit approved by the Board of Adjustment. A site development plan will be required for development on the commercial property, shown as Lot 51. A-1 zoning is also present to the east. Single-family developments exist to the north and south of this parcel while some larger residential lots exist east of the development, located in unincorporated Scott County (see Future Land Use and Current Zoning – Attachment B; Proposed Zoning – Attachment C).

A concept plan submitted with the initial annexation request aligns with the proposed preliminary plat (see Annexation Concept – Attachment D; Preliminary Plat – Attachment E). Portions of the property are in Special Flood Hazard Areas, and the applicant's development team has taken this fact into account for lot configuration of the single-family lots or commercial lot.

Future Land Use and Comprehensive Plan

As noted previously, the Future Land Use Map designates the area of the rezoning as multiple future land use categories. The proposed zoning and proposed uses are compatible and consistent with the Comprehensive Plan.

Multiple Comprehensive Plan goals are met by the proposed development including preserving environmental sensitive areas, implementing the annexation 7-point strategies, and enhancing community character with improved education services making Bettendorf a great place to live.

Lot Configuration and Zoning Compliance

A total of 85 single-family detached lots are proposed in the development, and all conform to the minimum bulk standards for the proposed R-2 district. Two lots are reserved for either the sanitary lift station (Lot 50) or future commercial (Lot 51). A total of seven outlots are associated with development and are reserved either for stormwater drainage, detention, or open space. The northern commercial lot is proposed to be indoor storage, which requires a Zoning Ordinance Text Amendment (see Case No. 25-018-ORD). The lot configurations are of sufficient size for the proposed uses and is located in an area that can be developed. All additional bulk standards and regulations have been sufficiently considered for the rezoning including floor area, height, and setbacks.

Utilities and Services

The development will be served by the Spencer Creek sanitary sewer lift station, currently under construction and shown as Lot 50 on the Preliminary Plat. Iowa American Water and MidAmerican Energy have capacity to extend water, gas, and electric to future developments in the area.

Thoroughfare Plan & Access

The Blackstone addition will be accessed via to local public streets, which will connect to existing roads west of the Forest Grove School House on Forest Grove Drive and north of the Pleasant Valley Community School District property on Wells Ferry Road. The development proposes a total of four cul-de-sacs, which are necessary given the steep topography of the area.

Sidewalks will be required on all streets within the subdivision and are shown on the plat. Outlot D will contain a trail connection from Black Oak Drive to the future Pleasant Valley Community School District development. The sidewalk will be constructed with the first phase of construction, which will allow future owners to be aware of its existence.

No improvements or sidewalks will be required at this time to Forest Grove Drive or Wells Ferry Road. Both roads have drainage ditches which prevents sidewalk construction in their current form.

Storm Water and Floodplain

The residential development reserves multiple outlots for storm water detention and drainage. Outlot F contains the Spencer Creek regulatory floodway and no alterations to this area can occur without prior approval from FEMA, IDNR, and Bettendorf's Floodplain Administration (see Floodplain Map – Attachment F). Local floodplain development permits are required for additional work in the floodplain fringe if not already permitted.

Construction Phasing

At this time, the development is proposed to be constructed in at least two phases. The preliminary plat outlines the first phase in red. Due to the number of single-family homes proposed in the first phase, Timber Ridge Lane will be required to be constructed as a fire access lane during the first phase. Each phase will platted as separate final plats.

Staff Recommendation

Given the evidence and reasons stated in the staff analysis of the request, staff recommends the Planning and Zoning Commission recommend <u>approval</u> of the proposed Preliminary Plat for the Blackstone addition (Case No. 25-019-PP).

Respectfully submitted,


Taylor Beswick Senior City Planner


Attachments:

Aerial Map - Attachment A
Future Land Use and Current Zoning - Attachment B
Proposed Zoning - Attachment C
Annexation Concept - Attachment D
Preliminary Plat - Attachment E
Floodplain Map - Attachment F




Case No. 25-019-PP Blackstone Addition Preliminary Plat Aerial - Attachment A









Case No. 25-019-PP Blackstone Addition Preliminary Plat Future Land Use & Zoning - Attachment B










REZONING EXHIBIT

WINDMILLER FOREST GROVE BETTENDORF, IOWA

PROJECT LOCATION MAP:



(NOT TO SCALE)

APPLICANT INFORMATION:

APPLICANT/OWNER: WINDMILLER DEVELOPMENT, LLC

P.O. BOX 790 BETTENDORF, IA 52722

PREPARED BY:

AXIOM CONSULTANTS, LLC C/O BRIAN BOELK 300 S. CLINTON STREET, UNIT 200 IOWA CITY, IOWA 52240 319-519-6220 BBOELK@AXIOM-CON.COM

LEGAL DESCRIPTION:

ZONED TO C-3:

BEING THE NORTHERN PORTION OF CORRECTED AUDITOR'S PARCEL A AS RECORDED IN 2024-5174 OF THE SCOTT COUNTY RECORDER'S OFFICE DESCRIBED AS:

BEGINNING AT THE NORTHWEST CORNER OF SAID CORRECTED AUDITOR'S PARCEL A; THENCE N87°43'35"E, 662.59 FEET; THENCE S81°51'18"E, 189.70 FEET; THENCE N86°32'59"E, 940.47; THENCE S20°07'51"E, 425.71 FEET; THENCE S78°05'05"W, 853.49 FEET; THENCE N70°28'47"W, 1161.59 FEET; THENCE N02°15'48"W, 131.87 FEET TO THE POINT OF BEGINNING.

ALL IN THE CITY OF BETTENDORF, SCOTT COUNTY, IOWA. DESCRIBED AREA CONTAINS 16.84 ACRES AND IS SUBJECT TO EASEMENTS AND OTHER RESTRICTIONS OF RECORD.

ZONED TO R-2:

BEING PART OF CORRECTED AUDITOR'S PARCEL A AS RECORDED IN 2024-5174, ALL OF AUDITOR'S PARCEL B AS RECORDED IN 2024-5420, AND ALL OF THE LEASE PARCEL AS RECORDED IN 2022-24374 OF THE SCOTT COUNTY RECORDER'S OFFICE, CITY OF BETTENDORF, SCOTT COUNTY, IOWA, EXCEPT THE NORTHERN PORTION OF SAID CORRECTED AUDITOR'S PARCEL A DESCRIBED AS:

BEGINNING AT THE NORTHWEST CORNER OF SAID CORRECTED AUDITOR'S PARCEL A; THENCE N87°43'35"E, 662.59 FEET; THENCE S81°51'18"E, 189.70 FEET; THENCE N86°32'59"E, 940.47; THENCE S20°07'51"E, 425.71 FEET; THENCE S78°05'05"W, 853.49 FEET; THENCE N70°28'47"W, 1161.59 FEET; THENCE N02°15'48"W, 131.87 FEET TO THE POINT OF BEGINNING.

ALL IN THE CITY OF BETTENDORF, SCOTT COUNTY, IOWA. DESCRIBED AREA CONTAINS 94.34 ACRES AND IS SUBJECT TO EASEMENTS AND OTHER RESTRICTIONS OF RECORD.

ZONING INFORMATION:


CURRENT ZONING:


A-1 AGRICULTURAL/URBAN RESERVE DISTRICT

PROPOSED ZONING:

C-3 GENERAL BUSINESS DISTRICT

R-2 SINGLE-FAMILY RESIDENCE DISTRICT





B


ISSUED FOR REVISED SUBMITTAL

DATE 03-05-2025 DESCRIPTION DATE

PROJECT NO. 22-0199

REZONING EXHIBIT


1 OF 1




PRELIMINARY PLAT **BLACKSTONE**

IN THE CITY OF BETTENDORF, SCOTT COUNTY, IOWA

LOCATION MAP





LEGAL DESCRIPTION

CORRECTED AUDITOR'S PARCEL A AS RECORDED IN 2024-5174, EXCEPT AUDITOR'S PARCEL B AS RECORDED IN 2024-5420 OF THE SCOTT COUNTY RECORDER'S OFFICE, IN THE CITY OF BETTENDORF, SCOTT COUNTY, IOWA.


GENERAL NOTES

- ALL IMPROVEMENTS ARE TO BE INSTALLED IN ACCORDANCE WITH THE LATEST CITY OF BETTENDORF STANDARD SPECIFICATIONS AND DETAIL DRAWINGS
- THE EXISTING ZONING FOR THE LOTS SHOWN ON THE SITE IS A-1.
- THE PROPOSED ZONING FOR ALL LOTS EXCEPT LOT 51 IS R-2. LOT 51 ZONING SHALL BE C-3.
- 4. REQUIRED SETBACKS ARE FOR R-2:


FRONT	SIDE	REA		
25'	5'	25		

- 5. MINIMUM LOT AREA 8,400 SF.
- 6. MINIMUM LOT WIDTH 65 FEET
- 7. MAX BUILDING HEIGHT 35', 2.5 STORIES MAX.
- 8. EASEMENTS FOR PLANNING PURPOSES. SUBJECT TO CHANGE WITH SITE DESIGN. TO BE INCORPORATED INTO FINAL PLAT OR EASEMENT EXHIBITS.
- 9. NO ACCESS TO WELLS FERRY ROAD FROM LOTS 77 OR 79.
- 10. LOTS 50, 51, AND 78 SHALL HAVE ACCESS TO WELLS FERRY ROAD.
- 11. ALL WATERMAIN IN SUBDIVISION TO BE 8". WATERMAIN ALONG WEST SIDE OF WELLS FERRY ROAD TO BE 16".
- 12. ALL SANITARY IN SUBDIVISION TO BE 8".
- 13. CITY REQUIRES FLOODWAY STAKING DURING CONSTRUCTION.
- 14. OUTLOT A TO CONSIST OF MAILBOX CLUSTER AND SUBDIVISION MONUMENT SIGN. NO OTHER STRUCTURES SHALL BE CONSTRUCTED WITHOUT PRIOR APPROVAL FROM THE CITY OF BETTENDORF.
- 15. OUTLOT B TO BE RESERVED FOR FUTURE CITY OF BETTENDORF RIGHT-OF-WAY.
- 16. SIDEWALK ON OUTLOT D IS REQUIRED TO BE CONSTRUCTED WITH FIRST ADDITION. OUTLOT D TO BE TRANSFERRED TO PV SCHOOL OWNERSHIP AFTER CONSTRUCTION OF SCHOOL

17.	7. THE INTENDED USE OF THE OUTLOT AND LETTERED LOTS WITHIN THE PLAT ARE AS FOLLOWS:								
	OUTLOT	INTENDED USE	RESPONSIBLE PARTY						
	OUTLOT A	MAILBOXES, SIGN AND OPEN SPACE	HOMEOWNER'S ASSOCIATION						
	OUTLOT B	OPEN SPACE	HOMEOWNER'S ASSOCIATION						
	OUTLOT C	DETENTION BASIN AND OPEN SPACE	HOMEOWNER'S ASSOCIATION						
	OUTLOT D	PUBLIC SIDEWALK AND SANITARY SEWER	HOMEOWNER'S ASSOCIATION/PV SCHOOLS						
	OUTLOT E	DETENTION BASIN AND OPEN SPACE	HOMEOWNER'S ASSOCIATION						
	OUTLOT F	FLOODWAY PARCEL	HOMEOWNER'S ASSOCIATION						
	OUTLOT G	DRAINAGEWAY AND OPEN SPACE	HOMEOWNER'S ASSOCIATION						
	OUTLOT H	DETENTION BASIN	HOMEOWNER'S ASSOCIATION						
	OUTLOT I	FLOODWAY PARCEL	HOMEOWNER'S ASSOCIATION						
	OUTLOT J	DETENTION BASIN AND OPEN SPACE	HOMEOWNER'S ASSOCIATION						
	OUTLOT K	DETENTION BASIN	HOMEOWNER'S ASSOCIATION						
	LOT 50	LIFT STATION	CITY OF BETTENDORF						
	LOT A	STREET RIGHT OF WAY	CITY OF BETTENDORF						
	LOT B	STREET RIGHT OF WAY	CITY OF BETTENDORF						
	LOT C	STREET RIGHT OF WAY	CITY OF BETTENDORF						







BL

ISSUED FOR REVISED SUBMITTAL #2 DATE 04-08-2025

DESCRIPTION DATE

REVISED SUBMITTAL

ESIGNED BY NB/JP CHECKED BY PROJECT NO. 22-0199

SHEET NAME |PRELIMINARY PLAT

IOWA CITY, IOWA 52240

APPLICANT: WINDMILLER DEVELOPMENT, LLC P.O. BOX 790

WINDMILLER DEVELOPMENT, LLC

OWNER:

P.O. BOX 790

PREPARED BY:

BETTENDORF, IA 52722

BETTENDORF, IA 52722

AXIOM CONSULTANTS, LLC

300 S CLINTON STREET, #200

83 0.39 AC 17,000 SF

6" PCC -

REQUIRED SEALCOAT FIRE ACCESS ROAD

-TO BE CONSTRUCTED WITH FIRST ADDITION

½" X 30" EPOXY

JOINTS) - 6" PAVEMENT AGGREGATE IDOT GRADATION 12 OR 14

BARS @ 30' ON CENTER ('L' OR 'K' 6" DRAINTILE -

N89° 03' 57"E

OUTLOTK


0.41 AC-

— IDOT GRADATION 29

☐ 3" MIN FOR SUBDRAIN


17,730 SF


1 OF 2





Case No. 25-019-PP Blackstone Addition Preliminary Plat Floodplain - Attachment F





Staff Report

Subject: Planning & Zoning Commission

Author: Taylor Beswick

Community Development **Department:**

Date: April 11, 2025

Case No.: 25-013-PP

Preliminary Plat for 27-lot residential subdivision, Ridgehaven Subdivision **Request:**

Location: North of Crow Creek Road (6500 Crow Creek Road)

Applicant: Adam Seitz DBA Pheasant Creek Estates, LLC

Current Zoning: R-2, Single Family Residence District

Future Land Use: NL, Neighborhood Light

24-009-REZ (Rezone A-1 to R-2) **Related Cases:**

Background Information & Facts

Adam Seitz is requesting a review of a preliminary plat of a 27-lot single-family residential subdivision. The property is located north of Crow Creek Road and east of The Settlement at Pigeon Creek Additions (see Aerial Map – Attachment A). The property was rezoned from A-1 to R-2 in early 2024 (Case No. 24-009-REZ) (see Future Land Use & Zoning Map – Attachment B). A detailed concept was part of the rezoning submittal, and the submitted preliminary plat is materially similar, with the addition of four more lots due to the acquisition of additional property (see Rezoning Concept – Attachment C). The property is one of the last undeveloped locations in this area, which has primarily been developed as single-family subdivisions, churches, or schools. Lots have been designed to utilize existing topography and preserve wooded areas (see <u>Preliminary Plat – Attachment D</u>).

Future Land Use and Comprehensive Plan

The area is designated for NL, Neighborhood Light and GW, Greenways on the Future Land Use Map which is consistent with the current R-2, Single-Family Residence District zoning. Areas designated for Greenways on the Future Land Use Map are located in wooded areas or the floodplain and have been shown in protected outlots on the preliminary plat. The development proposal also supports multiple goals of the Comprehensive Plan including expanding housing choices, enhancing community character, and promoting street connectivity with existing and future developments.

Lot Configuration and Zoning Compliance

Buildable lots range in size from 0.33 acres to 0.79 acres, which meet the minimum size for the R-2 Zoning District. Most if not all lots are configured for basement walkouts which works well with the existing topography of the site. The rear area of most lots is reserved for stormwater drainage and currently contain wooded terrain.

Pg. 1

Utilities and Services

The development will be served by Bettendorf sanitary sewer. Preliminary engineering has been reviewed by city staff and deemed sufficient for moving forward to full design. Iowa American Water and MidAmerican Energy have capacity to extend water, gas, and electric to future developments in the area.

Thoroughfare Plan & Access

One road (Ridgehaven Road) provides access to the development via Crow Creek Road. Due to the current topography, the road will contain a switchback on the southern end. Road profiles, radii, grades have been reviewed by city staff and meet adopted standards. The road will temporarily end at the northern boundary of the subdivision. Future development, north of this development will continue the road and connect it to Winfield Court. Pigeon Creek Trail is not proposed to connect to this development due to multiple property ownerships at and topography. Temporary turnaround easements are located on the northern lots (Lots 13 and 14) for service vehicles.

Sidewalks are proposed on both sides of Ridgehaven Road and will connect to an existing sidewalk on Crow Creek Road. Crow Creek Road contains a retaining wall of significant height and length. A retaining wall maintenance easement has been included on Lot 27 and Outlot B for any future work needed on the wall.

Stormwater & Floodplain

Stormwater is detained in three ponds in the subdivision which have been delineated into multiple outlots. Some property is in 100-year floodplain. Those areas are also shown in outlots.

Construction Phasing

The subdivision is currently proposed to be developed in a single phase, thus one final plat will be required.

Staff Recommendation

Given the evidence and reasons stated in the staff analysis of the request, staff recommends the Planning and Zoning Commission recommend approval of the proposed Preliminary Plat for Ridgehaven Subdivision (Case No. 25-013-PP).

Respectfully submitted,


Taylor Beswick Senior City Planner


Attachments:

Aerial Map – Attachment A
Future Land Use & Zoning Map – Attachment B
Rezoning Concept – Attachment C
Preliminary Plat – Attachment D




Case No. 25-013-PP Ridgehaven First Addition Preliminary Plat Aerial - Attachment A










Case No. 25-013-PP Ridgehaven First Addition **Preliminary Plat** Future Land Use & Zoning - Attachment B










P:\Davenport\2023\23-6093 Advance Home Inc - Odama Farm Survey\12.Civil\23-6093-XBASE-1-22-2024.dwg, 1/26/2024 11:12:15 AM, DWG To PDF.pc3



STAFF REPORT

Subject: 3346 Towne Pointe Drive

Author: Greg Beck

Department: Community Development

Date: April 11, 2024



Case No.: 25-015-SDP

Request: Site Development Plan

Location: 3346 Towne Pointe Drive

Legal Description: Lot 2, Crowne Pointe Seventh Addition and Lot 2, Crowne Pointe Fourth Addition

Parcel Numbers: 841537102 and 841537702

Applicant: Everest Homes, LLC

Current Zoning: C-2, Community Commercial District

Future Land Use: CC, Community Commercial

Background Information & Facts

Everest Homes, LLC is requesting approval of a site development plan for four townhouse buildings to be located at 3346 Towne Pointe Drive. This site consists of two lots of record: Lot 2, Crowne Pointe Fourth Addition and Lot 2, Crowne Point Seventh Addition.

Future Land Use and Comprehensive Plan

The Future Land Use Map designates Community Commercial as the land use designation for these lots and all adjacent lots. The proposed development is consistent with the comprehensive plan goal to expand housing choices and strengthen neighborhoods.

Lot Configuration & Zoning Compliance

The parcel is zoned C-2, which aligns with the CC future land use designation. Additionally, C-2 does allow the townhomes as a permitted use. The surrounding zoning classifications are C-2, Community Commercial District (west, east and south) and Planned Unit Development (north).

The site development plan shows three, 6-unit buildings and one, 7-unit building spanning the two lots for a total of 25 units. The townhouses are proposed as 3-story structures, with garages on the first floor. Building heights, setback and all other bulk standards are conforming. 34 multi-family units could be built on site as a maximum number. The petitioner is requesting 25 multi-family units.

Thoroughfare Plan & Access

Access to the site shall come from Towne Pointe Drive and Towne Pointe Center (private drive). Towne Pointe Drive connects to Belmont Road, which joins Devils Glen Road and Middle Road.

Utilities

Utilities connections are abundantly available to the site. Water supply will come from the east side of Towne Pointe Drive. Sanitary sewer will come from north of Towne Pointe Center. Electrical

service is available from the east and south. Gas and telecommunications service is supplied from the north side of the site. A utility easement on the east side of Lot 2, Crowne Pointe Seventh Addition shall be abandoned with the submittal of a plat of survey, prior to the issuing of building permits.

Pedestrian and Trail Access

Pedestrian access will be established along Towne Pointe Drive via a 4-foot-wide sidewalk with and ADA pad at its terminus. An ADA sidewalk pad shall be installed directly opposite at the corresponding sidewalk on the east side of Town Pointe Drive.

Off-Street Parking

Fifty parking spaces are available, meeting the minimum required by code. Each unit shall have a parking space in front of the garage and one inside the garage.

Stormwater Detention

Storm water will be directed north to Outlot A, Crowne Pointe Fourth Addition through the storm sewer connections.

Landscaping

Landscaping requirements are met by providing 4 tree factors on the east side of the lot facing Towne Pointe Drive and 2 tree factors for the vehicular use area.

Lighting

All site lighting shall follow City standards to be limited to illuminating the parcel.

Staff Recommendation

Staff recommends approval of the site development plan with the following conditions:

- 1. No planting of tree factors in easements is permitted.
- 2. ADA sidewalk pads are required to be placed to allow for a crossing to the sidewalk on the east side of Towne Pointe Drive from the sidewalk adjoining Lot 4, Crowne Pointe Fourth Addition.
- 3. A utility easement on the east side of Lot 2, Crowne Pointe Seventh Addition will be abandoned with the submittal of a plat of survey, prior to the issuing of building permits.
- 4. Due to the number of units, the proposed sanitary sewer will be required to be a public main. A sanitary sewer easement will need to be dedicated prior to the issuance of any building permits.

Greg Beck, City Planner


List of Attachments:


- A Aerial Location Map
- B FLUM and Zoning Map
- C Final Plat Crowne Pointe Fourth Addition
- D Final Plat Crowne Pointe Seventh Addition
- E Site Development Plan
- F Landscape Plan
- G Elevations



Case No. 25-015-SDP Lot 2, Crowne Pointe 4th/7th Add. Site Development Plan: Townhomes Buildings


Aerial - Attachment A










Case No. 25-015-SDP Lot 2, Crowne Pointe 4th/7th Add. Site Development Plan: Townhomes Buildings Future Land Use & Zoning - Attachment B

















10. DOG PARK 11. SUBDRAIN 12. TRASH ENCLOSURE 13. DETECTABLE WARNINGS

oricindesign.com

Client Name PANDIT ENTERPRISES

> Project Name **EVEREST**


HOMES **MULTI-FAMILY**

Location / Description

BETTENDORF. IOWA

Sheet Title

PROPOSED CONDITIONS



25-015 ATTACHMENT G



