

The Town of Conover is accepting sealed bids for the asphalt pavement of approximately 1685 ft. in the town of Conover for fiscal year 2022. This is for approximately 1,685 ft of Rush Rd. which is part of an LRIP Project. Schedule of Prices are available on the Town's website: townofconover.com/. Any questions on navigation of the website please contact the clerk's office at (715)479-8688. Bids must be received by 5:30 PM on May 12th, all bids will be opened at the Town Board Meeting that evening of March 12th at 6:00 pm. If you have questions, please contact the Town Foreman John Barnekow at 715-479-5420 or conoverhwyforeman@gmail.com.

The Town of Conover reserves the right to reject any and all bids, or to accept the bid deemed most advantageous to the town.

Please mail all bids to: Town of Conover

P.O. Box 115

Conover, WI 54519

Posted this day, April 21st, 2022. Kendra Lederer, Conover Clerk

SCHEDULE OF PRICES

PROJECT: Town of Conover
SITE: Rush Road – From E. Buckatabon Road to Katie Lane (LRIP)
TOTAL LENGTH – 1,685' = 0.32 Miles

ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT BID PRICE \$	TOTAL \$
MOBILIZATION	LUMP SUM	1		
PULVERIZE EXISTING ROADWAY, FULL WIDTH AND DEPTH OF EXISTING ASPHALT. GRADE AND COMPACT IN PREPARATION FOR CABC 26' WIDE.	PER MILE	0.32		
FURNISH, HAUL, PLACE AND COMPACT 4" CRUSHED AGGREGATE BASE COURSE, 26' WIDE.	CUBIC YARDS	680		
FURNISH, HAUL, PLACE AND COMPACT A 2-1/4" AVERAGE THICKNESS ASPHALT SURFACE, TYPE 4 LT58-28s, 20' WIDE. WIDEN CORNERS AND INSTALL 6" APRONS AT UNPAVED ENTRANCES.	TONS	485		
FURNISH, HAUL, PLACE AND COMPACT A 3' CRUSHED AGGREGATE BASE COURSE SHOULDER.	CUBIC YARDS	130		
CONSTRUCT PRIVATE ENTRANCES – UNPAVED. INCLUDES GRAVEL INTERSECTIONS.	EACH	12		
SAWCUT BUTT JOINTS WHERE NEW PAVEMENT JOINS EXISTING PAVEMENT.	LUMP SUM	1		
			TOTAL \$	