

BOROUGH OF FARMINGDALE

Regular Meeting - Tuesday, December 1, 2020

FLAG SALUTE, OPENING PRAYER, SUNSHINE STATEMENT

The meeting was called to order at 7:02 p.m. with the Flag Salute led by Mayor Daly. C/Linszky read the opening prayer. Mayor Daly read the Open Public Meetings Act Statement into the record.

ROLL CALL

PRESENT: Mayor Daly, C/Linszky, C/Steinfeld, C/Brandl, C/Corallo

ABSENT: C/Dyevoich and C/Sagan

PROCLAMATION – School Choice Week

Mayor Daly read the proclamation into the record as follows:

Borough of Farmingdale Proclamation School Choice Week

WHEREAS all children in the Borough of Farmingdale should have access to the highest-quality education possible; and,

WHEREAS the Borough of Farmingdale recognizes the important role that an effective education plays in preparing all students in Farmingdale to be successful adults; and,

WHEREAS quality education is critically important to the economic vitality of Farmingdale; and,

WHEREAS the Borough of Farmingdale and the surrounding areas are home to a multitude of high quality public and nonpublic schools from which parents can choose for their children, in addition to families who educate their children in the home; and

WHEREAS, educational variety not only helps to diversify our economy, but also enhances the vibrancy of our community; and,

WHEREAS, the Borough of Farmingdale has many high-quality teaching professionals in all types of school settings who are committed to educating our children; and,

WHEREAS, School Choice Week is celebrated across the country by millions of students, parents, educators, schools and organizations to raise awareness of the need for effective educational options.

NOW, THEREFORE, I, Mayor James A. Daly, do hereby recognize January 24 – January 30, 2021 as Farmingdale School Choice Week, and I call this observance to the attention of all of our citizens.

PUBLIC COMMENT - Agenda and Non-Agenda Items

Motion to open the meeting to the public by C/Linszky; seconded by C/Brandl

Voice Vote: AYE - C/Linszky, C/Steinfeld, C/Brandl, C/Corallo

ABSENT - C/Dyevoich, C/Sagan

An update from the Farmingdale Forever Citizen Action Group was provided. The Group is working toward the traffic and safety issues in town - specifically regarding speeding, distracted driving, and commercial truck traffic. A letter was shared which raised the concerns the Group wants addressed. Discussion followed regarding issues in town and the residents working together to address them through the Farmingdale Forever Group. Discussion continued on how to address the situation. A former crossing guard concurred the issues have been there for years.

Motion to close the meeting to the public by C/Linszky; seconded by C/Brandl.

Voice Vote: AYE - C/Linszky, C/Steinfeld, C/Brandl, C/Corallo,

ABSENT - C/Dyevoich, C/Sagan

MAYOR'S REPORT

Mayor Daly reported the Borough received their dividend from the Monmouth County JIF insurance which will be applied to the first installment of 2021. Council, the Code Enforcement Officer and the Planning Board must take DEP training; information will be sent to Councilmembers regarding what they have to do. Mayor Daly shared a thank you card from the Fire Department for the support of the 2020 golf outing.

COUNCIL REPORTS

Councilwoman Patricia Linszky

C/Linszky had no report. She is looking into storm water and sewer issues and will report back at a later date.

Councilman Don Steinfeld
C/Steinfeld reported progress.

Councilman George Dyevoich
C/Dyevoich was absent.

Councilman Erich Brandl
C/Brandl has communication moving forward to have the repairs done to the DPW building.

Councilwoman Kaaren Corallo
C/Corallo had no report.

Councilwoman Colleen Sagan
C/Sagan was absent.

APPROVAL OF MINUTES

Regular Meeting 11/10/2020

Motion to approve the minutes by C/Linszky; seconded by C/Brandl
Voice Vote: AYE - C/Linszky, C/Steinfeld, C/Brandl, C/Corallo,
ABSENT - C/Dyevoich, C/Sagan

OLD BUSINESS

A. ORDINANCE ADOPTION

1. ORDINANCE 05-2020 – STORMWATER CONTROL – *Public Hearing/Adoption*

Mayor Daly read the ordinance by title into the record

Motion to open the floor to the public on Ordinance 05-2020 by C/Linszky; seconded by C/Brandl

Voice Vote: AYE - C/Linszky, C/Steinfeld, C/Brandl, C/Corallo,
ABSENT - C/Dyevoich, C/Sagan

There were no comments from the public.

Mayor Daly gave an overview of the ordinance.

Motion to close the floor to the public on Ordinance 05-2020 by C/Linszky; seconded by C/Brandl

Voice Vote: AYE - C/Linszky, C/Steinfeld, C/Brandl, C/Corallo,
ABSENT - C/Dyevoich, C/Sagan

Motion to adopt Ordinance 05-2020 by C/Linszky; seconded by C/Brandl

Roll Call: AYE - C/Linszky, C/Steinfeld, C/Brandl, C/Corallo,
ABSENT - C/Dyevoich, C/Sagan

ORDINANCE 05-2020

STORMWATER CONTROL

BE IT ORDAINED by the Mayor and Council of the Borough of Farmingdale, County of Monmouth, State of New Jersey, that Section 25-57 Stormwater Management of the Borough Code shall be replaced in its entirety with the following:

25-57.1 Scope and Purpose:

A. Policy Statement

Flood control, groundwater recharge, and pollutant reduction shall be achieved through the use of stormwater management measures, including green infrastructure Best Management Practices (GI BMPs) and nonstructural stormwater management strategies. GI BMPs and low impact development (LID) should be utilized to meet the goal of maintaining natural hydrology to reduce stormwater runoff volume, reduce erosion, encourage infiltration and groundwater recharge, and reduce pollution. GI BMPs and LID should be developed based upon physical site conditions and the origin, nature and the anticipated quantity, or amount, of potential pollutants. Multiple stormwater management BMPs may be necessary to achieve the established performance standards for water quality, quantity, and groundwater recharge.

B. Purpose

The purpose of this ordinance is to establish minimum stormwater management requirements and controls for "major development," as defined below in Section II.

C. Applicability

1. This ordinance shall be applicable to the following major developments:

- a. Non-residential major developments; and
- b. Aspects of residential major developments that are not pre-empted by the Residential Site Improvement Standards at N.J.A.C. 5:21.

2. This ordinance shall also be applicable to all major developments undertaken by the Borough of Farmingdale.

D. Compatibility with Other Permit and Ordinance Requirements

Development approvals issued pursuant to this ordinance are to be considered an integral part of development approvals and do not relieve the applicant of the responsibility to secure required permits or approvals for activities regulated by any other applicable code, rule, act, or ordinance. In their interpretation and application, the provisions of this ordinance shall be held to be the minimum requirements for the promotion of the public health, safety, and general welfare.

This ordinance is not intended to interfere with, abrogate, or annul any other ordinances, rule or regulation, statute, or other provision of law except that, where any provision of this ordinance imposes restrictions different from those imposed by any other ordinance, rule or regulation, or other provision of law, the more restrictive provisions or higher standards shall control.

25-57.2 Definitions:

For the purpose of this ordinance, the following terms, phrases, words and their derivations shall have the meanings stated herein unless their use in the text of this Chapter clearly demonstrates a different meaning. When not inconsistent with the context, words used in the present tense include the future, words used in the plural number include the singular number, and words used in the singular number include the plural number. The word "shall" is always mandatory and not merely directory. The definitions below are the same as or based on the corresponding definitions in the Stormwater Management Rules at N.J.A.C. 7:8-1.2.

"CAFRA Centers, Cores or Nodes" means those areas with boundaries incorporated by reference or revised by the Department in accordance with N.J.A.C. 7:7-13.16.

"CAFRA Planning Map" means the map used by the Department to identify the location of Coastal Planning Areas, CAFRA centers, CAFRA cores, and CAFRA nodes. The CAFRA Planning Map is available on the Department's Geographic Information System (GIS).

"Community basin" means an infiltration system, sand filter designed to infiltrate, standard constructed wetland, or wet pond, established in accordance with N.J.A.C. 7:8-4.2(c)14, that is designed and constructed in accordance with the New Jersey Stormwater Best Management Practices Manual, or an alternate design, approved in accordance with N.J.A.C. 7:8-5.2(g), for an infiltration system, sand filter designed to infiltrate, standard constructed wetland, or wet pond and that complies with the requirements of this chapter.

"Compaction" means the increase in soil bulk density.

"Contributory drainage area" means the area from which stormwater runoff drains to a stormwater management measure, not including the area of the stormwater management measure itself.

"Core" means a pedestrian-oriented area of commercial and civic uses serving the surrounding municipality, generally including housing and access to public transportation.

"County review agency" means an agency designated by the County Board of Chosen Freeholders to review municipal stormwater management plans and implementing ordinance(s). The county review agency may either be:

1. A county planning agency or
2. A county water resource association created under N.J.S.A 58:16A-55.5, if the ordinance or resolution delegates authority to approve, conditionally approve, or disapprove municipal stormwater management plans and implementing ordinances.

"Department" means the Department of Environmental Protection.

"Designated Center" means a State Development and Redevelopment Plan Center as designated by the State Planning Commission such as urban, regional, town, village, or hamlet.

"Design engineer" means a person professionally qualified and duly licensed in New Jersey to perform engineering services that may include, but not necessarily be limited to, development of project requirements, creation and development of project design and preparation of drawings and specifications.

"Development" means the division of a parcel of land into two or more parcels, the construction, reconstruction, conversion, structural alteration, relocation or enlargement of any building or structure, any mining excavation or landfill, and any use or change in the use of any building or other structure, or land or extension of use of land, for which permission is required under the Municipal Land Use Law, N.J.S.A. 40:55D-1 *et seq.*

In the case of development of agricultural land, development means: any activity that requires a State permit, any activity reviewed by the County Agricultural Board (CAB) and the State Agricultural Development Committee (SADC), and municipal review of any activity not exempted by the Right to Farm Act, N.J.S.A 4:1C-1 *et seq.*

"Disturbance" means the placement or reconstruction of impervious surface or motor vehicle surface, or exposure and/or movement of soil or bedrock or clearing, cutting, or removing of vegetation. Milling and repaving is not considered disturbance for the purposes of this definition.

"Drainage area" means a geographic area within which stormwater, sediments, or dissolved materials drain to a particular receiving waterbody or to a particular point along a receiving waterbody.

"Environmentally constrained area" means the following areas where the physical alteration of the land is in some way restricted, either through regulation, easement, deed restriction or ownership such as: wetlands, floodplains, threatened and endangered species sites or designated habitats, and parks and preserves. Habitats of endangered or threatened species are identified using the Department's Landscape Project as approved by the Department's Endangered and Nongame Species Program.

"Environmentally critical area" means an area or feature which is of significant environmental value, including but not limited to: stream corridors, natural heritage priority sites, habitats of endangered or threatened species, large areas of contiguous open space or upland forest, steep slopes, and well head protection and groundwater recharge areas. Habitats of endangered or threatened species are identified using the Department's Landscape Project as approved by the Department's Endangered and Nongame Species Program.

"Empowerment Neighborhoods" means neighborhoods designated by the Urban Coordinating Council "in consultation and conjunction with" the New Jersey Redevelopment Authority pursuant to N.J.S.A 55:19-69.

"Erosion" means the detachment and movement of soil or rock fragments by water, wind, ice, or gravity.

"Green infrastructure" means a stormwater management measure that manages stormwater close to its source by:

1. Treating stormwater runoff through infiltration into subsoil;
2. Treating stormwater runoff through filtration by vegetation or soil; or
3. Storing stormwater runoff for reuse.

"HUC 14" or "hydrologic unit code 14" means an area within which water drains to a particular receiving surface water body, also known as a subwatershed, which is identified by a 14-digit hydrologic unit boundary designation, delineated within New Jersey by the United States Geological Survey.

"Impervious surface" means a surface that has been covered with a layer of material so that it is highly resistant to infiltration by water.

"Infiltration" is the process by which water seeps into the soil from precipitation.

"Lead planning agency" means one or more public entities having stormwater management planning authority designated by the regional stormwater management planning committee pursuant to N.J.A.C. 7:8-3.2, that serves as the primary representative of the committee.

"Major development" means an individual "development," as well as multiple developments that individually or collectively result in:

1. The disturbance of one or more acres of land since February 2, 2004;
2. The creation of one-quarter acre or more of "regulated impervious surface" since February 2, 2004;
3. The creation of one-quarter acre or more of "regulated motor vehicle surface" since March 2, 2021; or
4. A combination of 2 and 3 above that totals an area of one-quarter acre or more. The same surface shall not be counted twice when determining if the combination area equals one-quarter acre or more.

Major development includes all developments that are part of a common plan of development or sale (for example, phased residential development) that collectively or individually meet any one or more of paragraphs 1, 2, 3, or 4 above. Projects undertaken by any government agency that otherwise meet the definition of "major development" but which do not require approval under the Municipal Land Use Law, N.J.S.A. 40:55D-1 et seq., are also considered "major development."

"Motor vehicle" means land vehicles propelled other than by muscular power, such as automobiles, motorcycles, autocycles, and low speed vehicles. For the purposes of this definition, motor vehicle does not include farm equipment, snowmobiles, all-terrain vehicles, motorized wheelchairs, go-carts, gas buggies, golf carts, ski-slope grooming machines, or vehicles that run only on rails or tracks.

"Motor vehicle surface" means any pervious or impervious surface that is intended to be used by "motor vehicles" and/or aircraft, and is directly exposed to precipitation including, but not limited to, driveways, parking areas, parking garages, roads, racetracks, and runways.

"Municipality" means any city, borough, town, township, or village.

"New Jersey Stormwater Best Management Practices (BMP) Manual" or **"BMP Manual"** means the manual maintained by the Department providing, in part, design specifications, removal rates, calculation methods, and soil testing procedures approved by the Department as being capable of contributing to the achievement of the stormwater management standards specified in this chapter. The BMP Manual is periodically amended by the Department as necessary to provide design specifications on additional best management practices and new information on already included practices reflecting the best available current information regarding the particular practice and the Department's determination as to the ability of that best management practice to contribute to compliance with the standards contained in this chapter. Alternative stormwater management measures, removal rates, or calculation methods may be utilized, subject to any limitations specified in this chapter, provided the design engineer demonstrates to the municipality, in accordance with Section IV.F. of this ordinance and N.J.A.C. 7:8-5.2(g), that the proposed measure and its design will contribute to achievement of the design and performance standards established by this chapter.

"Node" means an area designated by the State Planning Commission concentrating facilities and activities which are not organized in a compact form.

"Nutrient" means a chemical element or compound, such as nitrogen or phosphorus, which is essential to and promotes the development of organisms.

"Person" means any individual, corporation, company, partnership, firm, association, political subdivision of this State and any state, interstate or Federal agency.

"Pollutant" means any dredged spoil, solid waste, incinerator residue, filter backwash, sewage, garbage, refuse, oil, grease, sewage sludge, munitions, chemical wastes, biological materials, medical wastes, radioactive substance (except those regulated under the Atomic Energy Act of 1954, as amended (42 U.S.C. §§ 2011 et seq.)), thermal waste, wrecked or discarded equipment, rock, sand, cellar dirt, industrial, municipal, agricultural, and construction waste or runoff, or other residue discharged directly or indirectly to the land, ground waters or surface waters of the State, or to a domestic treatment works. "Pollutant" includes both hazardous and nonhazardous pollutants.

"Recharge" means the amount of water from precipitation that infiltrates into the ground and is not evapotranspired.

"Regulated impervious surface" means any of the following, alone or in combination:

1. A net increase of impervious surface;
2. The total area of impervious surface collected by a new stormwater conveyance system (for the purpose of this definition, a "new stormwater conveyance system" is a stormwater conveyance system that is constructed where one did not exist immediately prior to its construction or an existing system for which a new discharge location is created);
3. The total area of impervious surface proposed to be newly collected by an existing stormwater conveyance system; and/or
4. The total area of impervious surface collected by an existing stormwater conveyance system where the capacity of that conveyance system is increased.

"Regulated motor vehicle surface" means any of the following, alone or in combination:

1. The total area of motor vehicle surface that is currently receiving water;
2. A net increase in motor vehicle surface; and/or quality treatment either by vegetation or soil, by an existing stormwater management measure, or by treatment at a wastewater treatment plant, where the water quality treatment will be modified or removed.

"Sediment" means solid material, mineral or organic, that is in suspension, is being transported, or has been moved from its site of origin by air, water or gravity as a product of erosion.

"Site" means the lot or lots upon which a major development is to occur or has occurred.

"Soil" means all unconsolidated mineral and organic material of any origin.

"State Development and Redevelopment Plan Metropolitan Planning Area (PA1)" means an area delineated on the State Plan Policy Map and adopted by the State Planning Commission that is intended to be the focus for much of the State's future redevelopment and revitalization efforts.

"State Plan Policy Map" is defined as the geographic application of the State Development and Redevelopment Plan's goals and statewide policies, and the official map of these goals and policies.

"Stormwater" means water resulting from precipitation (including rain and snow) that runs off the land's surface, is transmitted to the subsurface, or is captured by separate storm sewers or other sewage or drainage facilities, or conveyed by snow removal equipment.

"Stormwater management basin" means an excavation or embankment and related areas designed to retain stormwater runoff. A stormwater management basin may either be normally dry (that is, a detention basin or infiltration system), retain water in a permanent pool (a retention basin), or be planted mainly with wetland vegetation (most constructed stormwater wetlands).

"Stormwater management measure" means any practice, technology, process, program, or other method intended to control or reduce stormwater runoff and associated pollutants, or to induce or control the infiltration or groundwater recharge of stormwater or to eliminate illicit or illegal non-stormwater discharges into stormwater conveyances.

"Stormwater runoff" means water flow on the surface of the ground or in storm sewers, resulting from precipitation.

"Stormwater management planning agency" means a public body authorized by legislation to prepare stormwater management plans.

"Stormwater management planning area" means the geographic area for which a stormwater management planning agency is authorized to prepare stormwater management plans, or a specific portion of that area identified in a stormwater management plan prepared by that agency.

"Tidal Flood Hazard Area" means a flood hazard area in which the flood elevation resulting from the two-, 10-, or 100-year storm, as applicable, is governed by tidal flooding from the Atlantic Ocean. Flooding in a tidal flood hazard area may be contributed to, or influenced by, stormwater runoff from inland areas, but the depth of flooding generated by the tidal rise and fall of the Atlantic Ocean is greater than flooding from any fluvial sources. In some situations, depending upon the extent of the storm surge from a particular storm event, a flood hazard area may be tidal in the 100-year storm, but fluvial in more frequent storm events.

"Urban Coordinating Council Empowerment Neighborhood" means a neighborhood given priority access to State resources through the New Jersey Redevelopment Authority.

"Urban Enterprise Zones" means a zone designated by the New Jersey Enterprise Zone Authority pursuant to the New Jersey Urban Enterprise Zones Act, N.J.S.A. 52:27H-60 et. seq.

"Urban Redevelopment Area" is defined as previously developed portions of areas:

1. Delineated on the State Plan Policy Map (SPPM) as the Metropolitan Planning Area (PA1), Designated Centers, Cores or Nodes;
2. Designated as CAFRA Centers, Cores or Nodes;
3. Designated as Urban Enterprise Zones; and
4. Designated as Urban Coordinating Council Empowerment Neighborhoods.

"Water control structure" means a structure within, or adjacent to, a water, which intentionally or coincidentally alters the hydraulic capacity, the flood elevation resulting from the two-, 10-, or 100-year storm, flood hazard area limit, and/or floodway limit of the water. Examples of a water control structure may include a bridge, culvert, dam, embankment, ford (if above grade), retaining wall, and weir.

"Waters of the State" means the ocean and its estuaries, all springs, streams, wetlands, and bodies of surface or groundwater, whether natural or artificial, within the boundaries of the State of New Jersey or subject to its jurisdiction.

"Wetlands" or "wetland" means an area that is inundated or saturated by surface water or ground water at a frequency and duration sufficient to support, and that under normal circumstances does support, a prevalence of vegetation typically adapted for life in saturated soil conditions, commonly known as hydrophytic vegetation.

25-57.3 Design and Performance Standards for Stormwater Management Measures

- A. Stormwater management measures for major development shall be designed to provide erosion control, groundwater recharge, stormwater runoff quantity control, and stormwater runoff quality treatment as follows:
 1. The minimum standards for erosion control are those established under the Soil and Sediment Control Act, N.J.S.A. 4:24-39 et seq., and implementing rules at N.J.A.C. 2:90.
 2. The minimum standards for groundwater recharge, stormwater quality, and stormwater runoff quantity shall be met by incorporating green infrastructure.
- B. The standards in this ordinance apply only to new major development and are intended to minimize the impact of stormwater runoff on water quality and water quantity in receiving water bodies and maintain groundwater recharge. The standards do not apply to new major development to the extent that alternative design and performance standards are applicable under a regional stormwater management plan or Water Quality Management Plan adopted in accordance with Department rules.

25-57.4 Stormwater Management Requirements for Major Development

- A. The development shall incorporate a maintenance plan for the stormwater management measures incorporated into the design of a major development in accordance with Section X.
- B. Stormwater management measures shall avoid adverse impacts of concentrated flow on habitat for threatened and endangered species as documented in the Department's Landscape Project or Natural Heritage Database established under N.J.S.A. 13:18-15.147 through 15.150, particularly *Helonias bullata* (swamp pink) and/or *Clemmys muhlenbergi* (bog turtle).
- C. The following linear development projects are exempt from the groundwater recharge, stormwater runoff quality, and stormwater runoff quantity requirements of Section IV.P, Q and R:
 1. The construction of an underground utility line provided that the disturbed areas are revegetated upon completion;
 2. The construction of an aboveground utility line provided that the existing conditions are maintained to the maximum extent practicable; and
 3. The construction of a public pedestrian access, such as a sidewalk or trail with a maximum width of 14 feet, provided that the access is made of permeable material.
- D. A waiver from strict compliance from the green infrastructure, groundwater recharge, stormwater runoff quality, and stormwater runoff quantity requirements of Section IV.O, P, Q and R may be obtained for the enlargement of an existing public roadway or railroad; or the construction or enlargement of a public pedestrian access, provided that the following conditions are met:
 1. The applicant demonstrates that there is a public need for the project that cannot be accomplished by any other means;
 2. The applicant demonstrates through an alternatives analysis, that through the use of stormwater management measures, the option selected complies with the requirements of Section IV.O, P, Q and R to the maximum extent practicable;
 3. The applicant demonstrates that, in order to meet the requirements of Section IV.O, P, Q and R, existing structures currently in use, such as homes and buildings, would need to be condemned; and
 4. The applicant demonstrates that it does not own or have other rights to areas, including the potential to obtain through condemnation lands not falling under IV.D.3 above within the upstream drainage area of the receiving stream, that would provide additional opportunities to mitigate the requirements of Section IV.O, P, Q and R that were not achievable onsite.
- E. Tables 1 through 3 below summarize the ability of stormwater best management practices identified and described in the New Jersey Stormwater Best Management Practices Manual to satisfy the green infrastructure, groundwater recharge, stormwater runoff quality and stormwater runoff quantity standards specified in Section IV.O, P, Q and R. When designed in accordance with the most current version of the New Jersey Stormwater Best Management Practices Manual, the stormwater management measures found at N.J.A.C. 7:8-5.2 (f) Tables 5-1, 5-2 and 5-3 and listed below in Tables 1, 2 and 3 are presumed to be capable of providing stormwater controls for the design and performance standards as outlined in the tables below. Upon amendment of the New Jersey Stormwater Best Management Practices Manual to reflect additions or deletions of BMPs meeting these standards, or changes in the presumed performance of BMPs designed in accordance with the New Jersey Stormwater BMP Manual, the Department shall publish in

the New Jersey Register a notice of administrative change revising the applicable table. The most current version of the BMP Manual can be found on the Department's website at:

https://njstormwater.org/bmp_manual2.htm.

- F. Where the BMP tables in the NJ Stormwater Management Rule are different due to updates or amendments with the tables in this ordinance the BMP Tables in the Stormwater Management rule at N.J.A.C. 7:8-5.2(f) shall take precedence.

Table 1 Green Infrastructure BMPs for Groundwater Recharge, Stormwater Runoff Quality, and/or Stormwater Runoff Quantity				
Best Management Practice	Stormwater Runoff Quality TSS Removal Rate	Stormwater Runoff Quantity	Groundwater Recharge	Minimum Separation from Seasonal High Water
Cistern	0	Yes	No	--
Dry Well ^(a)	0	No	Yes	2
Grass Swale	50 or less	No	No	2 ^(e) 1 ^(f)
Green Roof	0	Yes	No	--
Manufactured Treatment	50 or 80	No	No	Dependent upon the
Pervious Paving System ^(a)	80	Yes	Yes ^(b) No ^(c)	2 ^(b) 1 ^(c)
Small-Scale Bioretention Basin ^(a)	80 or 90	Yes	Yes ^(b) No ^(c)	2 ^(b) 1 ^(c)
Small-Scale Infiltration Basin ^(a)	80	Yes	Yes	2
Small-Scale Sand Filter	80	Yes	Yes	2
Vegetative Filter Strip	60-80	No	No	--

(Notes corresponding to annotations ^(a) through ^(f) follow Table 3)

Table 2 Green Infrastructure BMPs for Stormwater Runoff Quantity (or for Groundwater Recharge and/or Stormwater Runoff Quality with a Waiver or Variance from N.J.A.C. 7:8-5.3)				
Best Management Practice	Stormwater Runoff Quality TSS Removal Rate (percent)	Stormwater Runoff Quantity	Groundwater Recharge	Minimum Separation from Seasonal High Water Table (feet)
Bioretention System	80 or 90	Yes	Yes ^(b) No ^(c)	2 ^(b) 1 ^(c)
Infiltration Basin	80	Yes	Yes	2
Sand Filter ^(b)	80	Yes	Yes	2
Standard Constructed Wetland	90	Yes	No	N/A
Wet Pond ^(d)	50-90	Yes	No	N/A

(Notes corresponding to annotations ^(b) through ^(d) follow Table 3)

Table 3

**BMPs for Groundwater Recharge, Stormwater Runoff Quality, and/or Stormwater Runoff Quantity
only with a Waiver or Variance from N.J.A.C. 7:8-5.3**

Best Management Practice	Stormwater Runoff Quality TSS Removal Rate (percent)	Stormwater Runoff Quantity	Groundwater Recharge	Minimum Separation from Seasonal High Water Table (feet)
Blue Roof	0	Yes	No	N/A
Extended Detention Basin	40-60	Yes	No	1
Manufactured Treatment Device ^(h)	50 or 80	No	No	Dependent upon the device
Sand Filter ^(c)	80	Yes	No	1
Subsurface Gravel Wetland	90	No	No	1
Wet Pond	50-90	Yes	No	N/A

Notes to Tables 1, 2, and 3:

- (a) subject to the applicable contributory drainage area limitation specified at Section IV.O.2;
- (b) designed to infiltrate into the subsoil;
- (c) designed with underdrains;
- (d) designed to maintain at least a 10-foot wide area of native vegetation along at least 50 percent of the shoreline and to include a stormwater runoff retention component designed to capture stormwater runoff for beneficial reuse, such as irrigation;
- (e) designed with a slope of less than two percent;
- (f) designed with a slope of equal to or greater than two percent;
- (g) manufactured treatment devices that meet the definition of green infrastructure at Section II;
- (h) manufactured treatment devices that do not meet the definition of green infrastructure at Section II.

G. An alternative stormwater management measure, alternative removal rate, and/or alternative method to calculate the removal rate may be used if the design engineer demonstrates the capability of the proposed alternative stormwater management measure and/or the validity of the alternative rate or method to the municipality. A copy of any approved alternative stormwater management measure, alternative removal rate, and/or alternative method to calculate the removal rate shall be provided to the Department in accordance with Section VI.B. Alternative stormwater management measures may be used to satisfy the requirements at Section IV.O only if the measures meet the definition of green infrastructure at Section II. Alternative stormwater management measures that function in a similar manner to a BMP listed at Section O.2 are subject to the contributory drainage area limitation specified at Section O.2 for that similarly functioning BMP. Alternative stormwater management measures approved in accordance with this subsection that do not function in a similar manner to any BMP listed at Section O.2 shall have a contributory drainage area less than or equal to 2.5 acres, except for alternative stormwater management measures that function similarly to cisterns, grass swales, green roofs, standard constructed wetlands, vegetative filter strips, and wet ponds, which are not subject to a contributory drainage area limitation. Alternative measures that function similarly to standard constructed wetlands or wet ponds shall not be used for compliance with the stormwater runoff quality standard unless a variance in accordance with N.J.A.C. 7:8-4.6 or a waiver from strict compliance in accordance with Section IV.D is granted from Section IV.O.

H. Whenever the stormwater management design includes one or more BMPs that will infiltrate stormwater into subsoil, the design engineer shall assess the hydraulic impact on the groundwater table and design the site, so as to avoid adverse hydraulic impacts. Potential adverse hydraulic impacts include, but are not limited to, exacerbating a naturally or seasonally high water table, so as to cause surficial ponding, flooding of basements, or interference with the proper operation of subsurface sewage disposal systems or other subsurface structures within the zone of influence of the groundwater mound, or interference with the proper functioning of the stormwater management measure itself.

I. Design standards for stormwater management measures are as follows:

1. Stormwater management measures shall be designed to take into account the existing site conditions, including, but not limited to, environmentally critical areas; wetlands; flood-prone areas; slopes; depth to seasonal high water table; soil type, permeability, and texture; drainage area and drainage patterns; and the presence of solution-prone carbonate rocks (limestone);
2. Stormwater management measures shall be designed to minimize maintenance, facilitate maintenance and repairs, and ensure proper functioning. Trash racks shall be installed at the intake to the outlet structure, as appropriate, and shall have parallel bars with one-inch spacing between the bars to the elevation of the water quality design storm. For elevations higher than the water quality design storm, the parallel bars at the outlet structure shall be spaced no greater than one-third the width of the diameter of the orifice or one-third the width of the weir, with a minimum spacing between bars of one inch and a maximum spacing between bars of six inches. In addition, the design of trash racks must comply with the requirements of Section VIII.C;
3. Stormwater management measures shall be designed, constructed, and installed to be strong, durable, and corrosion resistant. Measures that are consistent with the relevant portions of the Residential Site Improvement Standards at N.J.A.C. 5:21-7.3, 7.4, and 7.5 shall be deemed to meet this requirement;
4. Stormwater management BMPs shall be designed to meet the minimum safety standards for stormwater management BMPs at Section VIII; and
5. The size of the orifice at the intake to the outlet from the stormwater management BMP shall be a minimum of two and one-half inches in diameter.

- J. Manufactured treatment devices may be used to meet the requirements of this subchapter, provided the pollutant removal rates are verified by the New Jersey Corporation for Advanced Technology and certified by the Department. Manufactured treatment devices that do not meet the definition of green infrastructure at Section II may be used only under the circumstances described at Section IV.O.4.
- K. Any application for a new agricultural development that meets the definition of major development at Section II shall be submitted to the Soil Conservation District for review and approval in accordance with the requirements at Sections IV.O, P, Q and R and any applicable Soil Conservation District guidelines for stormwater runoff quantity and erosion control. For purposes of this subsection, "agricultural development" means land uses normally associated with the production of food, fiber, and livestock for sale. Such uses do not include the development of land for the processing or sale of food and the manufacture of agriculturally related products.
- L. If there is more than one drainage area, the groundwater recharge, stormwater runoff quality, and stormwater runoff quantity standards at Section IV.P, Q and R shall be met in each drainage area, unless the runoff from the drainage areas converge onsite and no adverse environmental impact would occur as a result of compliance with any one or more of the individual standards being determined utilizing a weighted average of the results achieved for that individual standard across the affected drainage areas.
- M. Any stormwater management measure authorized under the municipal stormwater management plan or ordinance shall be reflected in a deed notice recorded in the Office of the County Clerk. A form of deed notice shall be submitted to the municipality for approval prior to filing. The deed notice shall contain a description of the stormwater management measure(s) used to meet the green infrastructure, groundwater recharge, stormwater runoff quality, and stormwater runoff quantity standards at Section IV.O, P, Q and R and shall identify the location of the stormwater management measure(s) in NAD 1983 State Plane New Jersey FIPS 2900 US Feet or Latitude and Longitude in decimal degrees. The deed notice shall also reference the maintenance plan required to be recorded upon the deed pursuant to Section X.B.5. Prior to the commencement of construction, proof that the above required deed notice has been filed shall be submitted to the municipality. Proof that the required information has been recorded on the deed shall be in the form of either a copy of the complete recorded document or a receipt from the clerk or other proof of recordation provided by the recording office. However, if the initial proof provided to the municipality is not a copy of the complete recorded document, a copy of the complete recorded document shall be provided to the municipality within 180 calendar days of the authorization granted by the municipality.
- N. A stormwater management measure approved under the municipal stormwater management plan or ordinance may be altered or replaced with the approval of the municipality, if the municipality determines that the proposed alteration or replacement meets the design and performance standards pursuant to Section IV of this ordinance and provides the same level of stormwater management as the previously approved stormwater management measure that is being altered or replaced. If an alteration or replacement is approved, a revised deed notice shall be submitted to the municipality for approval and subsequently recorded with the Office of the County Clerk and shall contain a description and location of the stormwater management measure, as well as reference to the maintenance plan, in accordance with M above. Prior to the commencement of construction, proof that the above required deed notice has been filed shall be submitted to the municipality in accordance with M above.
- O. Green Infrastructure Standards
1. This subsection specifies the types of green infrastructure BMPs that may be used to satisfy the groundwater recharge, stormwater runoff quality, and stormwater runoff quantity standards.
 2. To satisfy the groundwater recharge and stormwater runoff quality standards at Section IV.P and Q, the design engineer shall utilize green infrastructure BMPs identified in Table 1 at Section IV.F. and/or an alternative stormwater management measure approved in accordance with Section IV.G. The following green infrastructure BMPs are subject to the following maximum contributory drainage area limitations:

Best Management Practice	Maximum Contributory Drainage Area
Dry Well	1 acre
Manufactured Treatment Device	2.5 acres
Pervious Pavement Systems	Area of additional inflow cannot exceed three times the area occupied by the
Small-scale Bioretention Systems	2.5 acres
Small-scale Infiltration Basin	2.5 acres
Small-scale Sand Filter	2.5 acres

3. To satisfy the stormwater runoff quantity standards at Section IV.R, the design engineer shall utilize BMPs from Table 1 or from Table 2 and/or an alternative stormwater management measure approved in accordance with Section IV.G.
 4. If a variance in accordance with N.J.A.C. 7:8-4.6 or a waiver from strict compliance in accordance with Section IV.D is granted from the requirements of this subsection, then BMPs from Table 1, 2, or 3, and/or an alternative stormwater management measure approved in accordance with Section IV.G may be used to meet the groundwater recharge, stormwater runoff quality, and stormwater runoff quantity standards at Section IV.P, Q and R.
 5. For separate or combined storm sewer improvement projects, such as sewer separation, undertaken by a government agency or public utility (for example, a sewerage company), the requirements of this subsection shall only apply to areas owned in fee simple by the government agency or utility, and areas within a right-of-way or easement held or controlled by the government agency or utility; the entity shall not be required to obtain additional property or property rights to fully satisfy the requirements of this subsection. Regardless of the amount of area of a separate or combined storm sewer improvement project subject to the green infrastructure requirements of this subsection, each project shall fully comply with the applicable groundwater recharge, stormwater runoff quality control, and stormwater runoff quantity standards at Section IV.P, Q and R, unless the project is granted a waiver from strict compliance in accordance with Section IV.D.
- P. Groundwater Recharge Standards
1. This subsection contains the minimum design and performance standards for groundwater recharge as follows:
 2. The design engineer shall, using the assumptions and factors for stormwater runoff and groundwater recharge calculations at Section V, either:

- i. Demonstrate through hydrologic and hydraulic analysis that the site and its stormwater management measures maintain 100 percent of the average annual pre-construction groundwater recharge volume for the site; or
 - ii. Demonstrate through hydrologic and hydraulic analysis that the increase of stormwater runoff volume from pre-construction to post-construction for the 2-year storm is infiltrated.
3. This groundwater recharge requirement does not apply to projects within the "urban redevelopment area," or to projects subject to 4 below.
 4. The following types of stormwater shall not be recharged:
 - i. Stormwater from areas of high pollutant loading. High pollutant loading areas are areas in industrial and commercial developments where solvents and/or petroleum products are loaded/unloaded, stored, or applied, areas where pesticides are loaded/unloaded or stored; areas where hazardous materials are expected to be present in greater than "reportable quantities" as defined by the United States Environmental Protection Agency (EPA) at 40 CFR 302.4; areas where recharge would be inconsistent with Department approved remedial action work plan or landfill closure plan and areas with high risks for spills of toxic materials, such as gas stations and vehicle maintenance facilities; and
 - ii. Industrial stormwater exposed to "source material." "Source material" means any material(s) or machinery, located at an industrial facility, that is directly or indirectly related to process, manufacturing or other industrial activities, which could be a source of pollutants in any industrial stormwater discharge to groundwater. Source materials include, but are not limited to, raw materials; intermediate products; final products; waste materials; by-products; industrial machinery and fuels, and lubricants, solvents, and detergents that are related to process, manufacturing, or other industrial activities that are exposed to stormwater.

Q. Stormwater Runoff Quality Standards

1. This subsection contains the minimum design and performance standards to control stormwater runoff quality impacts of major development. Stormwater runoff quality standards are applicable when the major development results in an increase of one-quarter acre or more of regulated motor vehicle surface.
2. Stormwater management measures shall be designed to reduce the post-construction load of total suspended solids (TSS) in stormwater runoff generated from the water quality design storm as follows:
 - i. Eighty percent TSS removal of the anticipated load, expressed as an annual average shall be achieved for the stormwater runoff from the net increase of motor vehicle surface.
 - ii. If the surface is considered regulated motor vehicle surface because the water quality treatment for an area of motor vehicle surface that is currently receiving water quality treatment either by vegetation or soil, by an existing stormwater management measure, or by treatment at a wastewater treatment plant is to be modified or removed, the project shall maintain or increase the existing TSS removal of the anticipated load expressed as an annual average.
3. The requirement to reduce TSS does not apply to any stormwater runoff in a discharge regulated under a numeric effluent limitation for TSS imposed under the New Jersey Pollutant Discharge Elimination System (NJPDES) rules, N.J.A.C. 7:14A, or in a discharge specifically exempt under a NJPDES permit from this requirement. Every major development, including any that discharge into a combined sewer system, shall comply with 2 above, unless the major development is itself subject to a NJPDES permit with a numeric effluent limitation for TSS or the NJPDES permit to which the major development is subject exempts the development from a numeric effluent limitation for TSS.
4. The water quality design storm is 1.25 inches of rainfall in two hours. Water quality calculations shall take into account the distribution of rain from the water quality design storm, as reflected in Table 4, below. The calculation of the volume of runoff may take into account the implementation of stormwater management measures.

Table 4 - Water Quality Design Storm Distribution

Time (Minutes)	Cumulative Rainfall (Inches)	Time (Minutes)	Cumulative Rainfall (Inches)	Time (Minutes)	Cumulative Rainfall (Inches)
1	0.00166	41	0.1728	81	1.0906
2	0.00332	42	0.1796	82	1.0972
3	0.00498	43	0.1864	83	1.1038
4	0.00664	44	0.1932	84	1.1104
5	0.00830	45	0.2000	85	1.1170
6	0.00996	46	0.2117	86	1.1236
7	0.01162	47	0.2233	87	1.1302
8	0.01328	48	0.2350	88	1.1368
9	0.01494	49	0.2466	89	1.1434
10	0.01660	50	0.2583	90	1.1500
11	0.01828	51	0.2783	91	1.1550
12	0.01996	52	0.2983	92	1.1600
13	0.02164	53	0.3183	93	1.1650
14	0.02332	54	0.3383	94	1.1700
15	0.02500	55	0.3583	95	1.1750
16	0.03000	56	0.4116	96	1.1800
17	0.03500	57	0.4650	97	1.1850
18	0.04000	58	0.5183	98	1.1900
19	0.04500	59	0.5717	99	1.1950
20	0.05000	60	0.6250	100	1.2000
21	0.05500	61	0.6783	101	1.2050
22	0.06000	62	0.7317	102	1.2100
23	0.06500	63	0.7850	103	1.2150
24	0.07000	64	0.8384	104	1.2200
25	0.07500	65	0.8917	105	1.2250
26	0.08000	66	0.9117	106	1.2267
27	0.08500	67	0.9317	107	1.2284
28	0.09000	68	0.9517	108	1.2300
29	0.09500	69	0.9717	109	1.2317
30	0.10000	70	0.9917	110	1.2334
31	0.10660	71	1.0034	111	1.2351
32	0.11320	72	1.0150	112	1.2367
33	0.11980	73	1.0267	113	1.2384
34	0.12640	74	1.0383	114	1.2400
35	0.13300	75	1.0500	115	1.2417
36	0.13960	76	1.0568	116	1.2434
37	0.14620	77	1.0636	117	1.2450
38	0.15280	78	1.0704	118	1.2467
39	0.15940	79	1.0772	119	1.2483
40	0.16600	80	1.0840	120	1.2500

5. If more than one BMP in series is necessary to achieve the required 80 percent TSS reduction for a site, the applicant shall utilize the following formula to calculate TSS reduction:

$$R = A + B - (A \times B) / 100,$$

Where
 R = total TSS Percent Load Removal from application of both BMPs, and
 A = the TSS Percent Removal Rate applicable to the first BMP
 B = the TSS Percent Removal Rate applicable to the second BMP.
6. Stormwater management measures shall also be designed to reduce, to the maximum extent feasible, the post-construction nutrient load of the anticipated load from the developed site in stormwater runoff generated from the water quality design storm. In achieving reduction of nutrients to the maximum extent feasible, the design of the site shall include green infrastructure BMPs that optimize nutrient removal while still achieving the performance standards in Section IV.P, Q and R.
7. In accordance with the definition of FW1 at N.J.A.C. 7:9B-1.4, stormwater management measures shall be designed to prevent any increase in stormwater runoff to waters classified as FW1.
8. The Flood Hazard Area Control Act Rules at N.J.A.C. 7:13-4.1(c)1 establish 300-foot riparian zones along Category One waters, as designated in the Surface Water Quality Standards at N.J.A.C. 7:9B, and certain upstream tributaries to Category One waters. A person shall not undertake a major development that is located within or discharges into a 300-foot riparian zone without prior authorization from the Department under N.J.A.C. 7:13.
9. Pursuant to the Flood Hazard Area Control Act Rules at N.J.A.C. 7:13-11.2(j)3.i, runoff from the water quality design storm that is discharged within a 300-foot riparian zone shall be treated in accordance with this subsection to reduce the post-construction load of total suspended solids by 95 percent of the anticipated load from the developed site, expressed as an annual average.
10. The stormwater runoff quality standards do not apply to the construction of one individual single-family dwelling, provided that it is not part of a larger development or subdivision that has received preliminary or final site plan approval prior to December 3, 2018, and that the motor vehicle surfaces are made of permeable material(s) such as gravel, dirt, and/or shells.

R. Stormwater Runoff Quantity Standards

1. This subsection contains the minimum design and performance standards to control stormwater runoff quantity impacts of major development.
2. In order to control stormwater runoff quantity impacts, the design engineer shall, using the assumptions and factors for stormwater runoff calculations at Section V, complete one of the following:
 - i. Demonstrate through hydrologic and hydraulic analysis that for stormwater leaving the site, post-construction runoff hydrographs for the 2-, 10-, and 100-year storm events do not exceed, at any point in time, the pre-construction runoff hydrographs for the same storm events;
 - ii. Demonstrate through hydrologic and hydraulic analysis that there is no increase, as compared to the pre-construction condition, in the peak runoff rates of stormwater leaving the site for the 2-, 10- and 100-year storm events and that the increased volume or change in timing of stormwater runoff will not increase flood damage at or downstream of the site. This analysis shall include the analysis of impacts of existing land uses and projected land uses assuming full development under existing zoning and land use ordinances in the drainage area;
 - iii. Design stormwater management measures so that the post-construction peak runoff rates for the 2-, 10- and 100-year storm events are 50, 75 and 80 percent, respectively, of the pre-construction peak runoff rates. The percentages apply only to the post-construction stormwater runoff that is attributable to the portion of the site on which the proposed development or project is to be constructed; or
 - iv. In tidal flood hazard areas, stormwater runoff quantity analysis in accordance with 2.i, ii and iii above is required unless the design engineer demonstrates through hydrologic and hydraulic analysis that the increased volume, change in timing, or increased rate of the stormwater runoff, or any combination of the three will not result in additional flood damage below the point of discharge of the major development. No analysis is required if the stormwater is discharged directly into any ocean, bay, inlet, or the reach of any watercourse between its confluence with an ocean, bay, or inlet and downstream of the first water control structure.
3. The stormwater runoff quantity standards shall be applied at the site's boundary to each abutting lot, roadway, watercourse, or receiving storm sewer system.

25-57.5 Calculation of Stormwater Runoff and Groundwater Recharge:

A. Stormwater runoff shall be calculated in accordance with the following:

1. The design engineer shall calculate runoff using one of the following methods:
 - i. The USDA Natural Resources Conservation Service (NRCS) methodology, including the NRCS Runoff Equation and Dimensionless Unit Hydrograph, as described in Chapters 7, 9, 10, 15 and 16 Part 630, Hydrology National Engineering Handbook, incorporated herein by reference as amended and supplemented. This methodology is additionally described in *Technical Release 55 - Urban Hydrology for Small Watersheds* (TR-55), dated June 1986, incorporated herein by reference as amended and supplemented. Information regarding the methodology is available from the Natural Resources Conservation Service website at: https://www.nrcs.usda.gov/Internet/FSE_DOCUMENTS/stelprdb1044171.pdf or at United States Department of Agriculture Natural Resources Conservation Service, 220 Davison Avenue, Somerset, New Jersey 08873; or
 - ii. The Rational Method for peak flow and the Modified Rational Method for hydrograph computations. The rational and modified rational methods are described in "Appendix A-9 Modified Rational Method" in the Standards for Soil Erosion and Sediment Control in New Jersey, January 2014. This document is available from the State Soil Conservation Committee or any of the Soil Conservation Districts listed at N.J.A.C. 2:90-1.3(a)3. The location, address, and telephone number for each Soil Conservation District is available from the State Soil Conservation Committee, PO Box 330, Trenton, New Jersey 08625. The document is also available at: <http://www.nj.gov/agriculture/divisions/anr/pdf/2014NJSoilErosionControlStandardsComplete.pdf>.
2. For the purpose of calculating runoff coefficients and groundwater recharge, there is a presumption that the pre-construction condition of a site or portion thereof is a wooded land use with good hydrologic condition. The term "runoff coefficient" applies to both the NRCS methodology above at Section V.A.1.i and the Rational and Modified Rational Methods at Section V.A.1.ii. A runoff coefficient or a groundwater recharge land cover for an existing condition may be used on all or a portion of the site if the design engineer verifies that the hydrologic condition has existed on the site or portion of the site for at least five years without interruption prior to the time of application. If more than one land cover has existed

on the site during the five years immediately prior to the time of application, the land cover with the lowest runoff potential shall be used for the computations. In addition, there is the presumption that the site is in good hydrologic condition (if the land use type is pasture, lawn, or park), with good cover (if the land use type is woods), or with good hydrologic condition and conservation treatment (if the land use type is cultivation).

3. In computing pre-construction stormwater runoff, the design engineer shall account for all significant land features and structures, such as ponds, wetlands, depressions, hedgerows, or culverts, that may reduce pre-construction stormwater runoff rates and volumes.
4. In computing stormwater runoff from all design storms, the design engineer shall consider the relative stormwater runoff rates and/or volumes of pervious and impervious surfaces separately to accurately compute the rates and volume of stormwater runoff from the site. To calculate runoff from unconnected impervious cover, urban impervious area modifications as described in the NRCS *Technical Release 55 – Urban Hydrology for Small Watersheds* or other methods may be employed.
5. If the invert of the outlet structure of a stormwater management measure is below the flood hazard design flood elevation as defined at N.J.A.C. 7:13, the design engineer shall take into account the effects of tailwater in the design of structural stormwater management measures.

B. Groundwater recharge may be calculated in accordance with the following:

The New Jersey Geological Survey Report GSR-32, A Method for Evaluating

Groundwater-Recharge Areas in New Jersey, incorporated herein by reference as amended and supplemented. Information regarding the methodology is available from the New Jersey Stormwater Best Management Practices Manual; at the New Jersey Geological and Water Survey website at: <https://www.nj.gov/dep/njgs/pricelst/gsr32.pdf> or at New Jersey Geological and Water Survey, 29 Arctic Parkway, PO Box 420 Mail Code 29-01, Trenton, New Jersey 08625-0420.

25-57.6 Sources for Technical Guidance:


- A. Technical guidance for stormwater management measures can be found in the documents listed below, which are available to download from the Department's website at: http://www.nj.gov/dep/stormwater/bmp_manual2.htm.
 1. Guidelines for stormwater management measures are contained in the New Jersey Stormwater Best Management Practices Manual, as amended and supplemented. Information is provided on stormwater management measures such as, but not limited to, those listed in Tables 1, 2, and 3.
 2. Additional maintenance guidance is available on the Department's website at: https://www.njstormwater.org/maintenance_guidance.htm.
- B. Submissions required for review by the Department should be mailed to:
The Division of Water Quality, New Jersey Department of Environmental Protection, Mail Code 401-02B, PO Box 420, Trenton, New Jersey 08625-0420.

25-57.7 Solids and Floatable Materials Control Standards:

- A. Site design features identified under Section IV.F above, or alternative designs in accordance with Section IV.G above, to prevent discharge of trash and debris from drainage systems shall comply with the following standard to control passage of solid and floatable materials through storm drain inlets. For purposes of this paragraph, "solid and floatable materials" means sediment, debris, trash, and other floating, suspended, or settleable solids. For exemptions to this standard see Section VII.A.2 below.
 1. Design engineers shall use one of the following grates whenever they use a grate in pavement or another ground surface to collect stormwater from that surface into a storm drain or surface water body under that grate:
 - i. The New Jersey Department of Transportation (NJDOT) bicycle safe grate, which is described in Chapter 2.4 of the NJDOT Bicycle Compatible Roadways and Bikeways Planning and Design Guidelines; or
 - ii. A different grate, if each individual clear space in that grate has an area of no more than seven (7.0) square inches, or is no greater than 0.5 inches across the smallest dimension.
Examples of grates subject to this standard include grates in grate inlets, the grate portion (non-curb-opening portion) of combination inlets, grates on storm sewer manholes, ditch grates, trench grates, and grates of spacer bars in slotted drains. Examples of ground surfaces include surfaces of roads (including bridges), driveways, parking areas, bikeways, plazas, sidewalks, lawns, fields, open channels, and stormwater system floors used to collect stormwater from the surface into a storm drain or surface water body.
 - iii. For curb-opening inlets, including curb-opening inlets in combination inlets, the clear space in that curb opening, or each individual clear space if the curb opening has two or more clear spaces, shall have an area of no more than seven (7.0) square inches, or be no greater than two (2.0) inches across the smallest dimension.
 2. The standard in A.1. above does not apply:
 - i. Where each individual clear space in the curb opening in existing curb-opening inlet does not have an area of more than nine (9.0) square inches;
 - ii. Where the municipality agrees that the standards would cause inadequate hydraulic performance that could not practicably be overcome by using additional or larger storm drain inlets;
 - iii. Where flows from the water quality design storm as specified in N.J.A.C. 7:8 are conveyed through any device (e.g., end of pipe netting facility, manufactured treatment device, or a catch basin hood) that is designed, at a minimum, to prevent delivery of all solid and floatable materials that could not pass through one of the following:
 - a. A rectangular space four and five-eighths (4.625) inches long and one and one-half (1.5) inches wide (this option does not apply for outfall netting facilities); or
 - b. A bar screen having a bar spacing of 0.5 inches.
Note that these exemptions do not authorize any infringement of requirements in the Residential Site Improvement Standards for bicycle safe grates in new residential development (N.J.A.C. 5:21-4.18(b)2 and 7.4(b)1).
 - iv. Where flows are conveyed through a trash rack that has parallel bars with one-inch (1 inch) spacing between the bars, to the elevation of the Water Quality Design Storm as specified in N.J.A.C. 7:8; or
 - v. Where the New Jersey Department of Environmental Protection determines, pursuant to the New Jersey Register of Historic Places Rules at N.J.A.C. 7:4-7.2(c), that action to meet this standard is an undertaking that constitutes an encroachment or will damage or destroy the New Jersey Register listed historic property.

25-57.8 Safety Standards for Stormwater Management Basins:

- A. This section sets forth requirements to protect public safety through the proper design and operation of stormwater management basins. This section applies to any new stormwater management basin.
- B. The provisions of this section are not intended to preempt more stringent municipal or county safety requirements for new or existing stormwater management basins. Municipal and county stormwater management plans and ordinances may, pursuant to their authority, require existing stormwater management basins to be retrofitted to meet one or more of the safety standards in Section VIII.C.1, VIII.C.2, and VIII.C.3 for trash racks, overflow grates, and escape provisions at outlet structures.
- C. Requirements for Trash Racks, Overflow Grates and Escape Provisions
1. A trash rack is a device designed to catch trash and debris and prevent the clogging of outlet structures. Trash racks shall be installed at the intake to the outlet from the stormwater management basins to ensure proper functioning of the basins outlets in accordance with the following:
 - i. The trash rack shall have parallel bars, with no greater than six-inch spacing between the bars;
 - ii. The trash rack shall be designed so as not to adversely affect the hydraulic performance of the outlet pipe or structure;
 - iii. The average velocity of flow through a clean trash rack is not to exceed 2.5 feet per second under the full range of stage and discharge. Velocity is to be computed on the basis of the net area of opening through the rack; and
 - iv. The trash rack shall be constructed of rigid, durable, and corrosion resistant material and designed to withstand a perpendicular live loading of 300 pounds per square foot.
 2. An overflow grate is designed to prevent obstruction of the overflow structure. If an outlet structure has an overflow grate, such grate shall meet the following requirements:
 - i. The overflow grate shall be secured to the outlet structure but removable for emergencies and maintenance.
 - ii. The overflow grate spacing shall be no less than two inches across the smallest dimension.
 - iii. The overflow grate shall be constructed and installed to be rigid, durable, and corrosion resistant, and shall be designed to withstand a perpendicular live loading of 300 pounds per square foot.
 3. Stormwater management basins shall include escape provisions as follows:
 - i. If a stormwater management basin has an outlet structure, escape provisions shall be incorporated in or on the structure. Escape provisions include the installation of permanent ladders, steps, rungs, or other features that provide easily accessible means of egress from stormwater management basins. With the prior approval of the municipality pursuant to VIII.C, a free-standing outlet structure may be exempted from this requirement;
 - ii. Safety ledges shall be constructed on the slopes of all new stormwater management basins having a permanent pool of water deeper than two and one-half feet. Safety ledges shall be comprised of two steps. Each step shall be four to six feet in width. One step shall be located approximately two and one-half feet below the permanent water surface, and the second step shall be located one to one and one-half feet above the permanent water surface. See VIII.E for an illustration of safety ledges in a stormwater management basin; and
 - iii. In new stormwater management basins, the maximum interior slope for an earthen dam, embankment, or berm shall not be steeper than three horizontal to one vertical.
- D. Variance or Exemption from Safety Standard
A variance or exemption from the safety standards for stormwater management basins may be granted only upon a written finding by the municipality that the variance or exemption will not constitute a threat to public safety.
- E. Safety Ledge Illustration
Elevation View –Basin Safety Ledge Configuration

**25-57.9 Requirements for a Site Development Stormwater Plan:**

- A. Submission of Site Development Stormwater Plan
1. Whenever an applicant seeks municipal approval of a development subject to this ordinance, the applicant shall submit all of the required components of the Checklist for the Site Development Stormwater Plan at Section IX.C below as part of the submission of the application for approval.
 2. The applicant shall demonstrate that the project meets the standards set forth in this ordinance.

3. The applicant shall submit eight copies of the materials listed in the checklist for site development stormwater plans in accordance with Section IX.C of this ordinance.
- B. **Site Development Stormwater Plan Approval**
The applicant's Site Development project shall be reviewed as a part of the review process by the municipal board or official from which municipal approval is sought. That municipal board or official shall consult the municipality's review engineer to determine if all of the checklist requirements have been satisfied and to determine if the project meets the standards set forth in this ordinance.
- C. **Submission of Site Development Stormwater Plan**
The following information shall be required:
1. **Topographic Base Map**
The reviewing engineer may require upstream tributary drainage system information as necessary. It is recommended that the topographic base map of the site be submitted which extends a minimum of 200 feet beyond the limits of the proposed development, at a scale of 1"=200' or greater, showing 2-foot contour intervals. The map as appropriate may indicate the following: existing surface water drainage, shorelines, steep slopes, soils, erodible soils, perennial or intermittent streams that drain into or upstream of the Category One waters, wetlands and flood plains along with their appropriate buffer strips, marshlands and other wetlands, pervious or vegetative surfaces, existing man-made structures, roads, bearing and distances of property lines, and significant natural and manmade features not otherwise shown.
 2. **Environmental Site Analysis**
A written and graphic description of the natural and man-made features of the site and its surroundings should be submitted. This description should include a discussion of soil conditions, slopes, wetlands, waterways and vegetation on the site. Particular attention should be given to unique, unusual, or environmentally sensitive features and to those that provide particular opportunities or constraints for development.
 3. **Project Description and Site Plans**
A map (or maps) at the scale of the topographical base map indicating the location of existing and proposed buildings roads, parking areas, utilities, structural facilities for stormwater management and sediment control, and other permanent structures. The map(s) shall also clearly show areas where alterations will occur in the natural terrain and cover, including lawns and other landscaping, and seasonal high groundwater elevations. A written description of the site plan and justification for proposed changes in natural conditions shall also be provided.
 4. **Land Use Planning and Source Control Plan**
This plan shall provide a demonstration of how the goals and standards of Sections III through V are being met. The focus of this plan shall be to describe how the site is being developed to meet the objective of controlling groundwater recharge, stormwater quality and stormwater quantity problems at the source by land management and source controls whenever possible.
 5. **Stormwater Management Facilities Map**
The following information, illustrated on a map of the same scale as the topographic base map, shall be included:
 - i. Total area to be disturbed, paved or built upon, proposed surface contours, land area to be occupied by the stormwater management facilities and the type of vegetation thereon, and details of the proposed plan to control and dispose of stormwater.
 - ii. Details of all stormwater management facility designs, during and after construction, including discharge provisions, discharge capacity for each outlet at different levels of detention and emergency spillway provisions with maximum discharge capacity of each spillway.
 6. **Calculations**
 - i. Comprehensive hydrologic and hydraulic design calculations for the pre-development and post-development conditions for the design storms specified in Section IV of this ordinance.
 - ii. When the proposed stormwater management control measures depend on the hydrologic properties of soils or require certain separation from the seasonal high water table, then a soils report shall be submitted. The soils report shall be based on onsite boring logs or soil pit profiles. The number and location of required soil borings or soil pits shall be determined based on what is needed to determine the suitability and distribution of soils present at the location of the control measure.
 7. **Maintenance and Repair Plan**
The design and planning of the stormwater management facility shall meet the maintenance requirements of Section X.
 8. **Waiver from Submission Requirements**
The municipal official or board reviewing an application under this ordinance may, in consultation with the municipality's review engineer, waive submission of any of the requirements in Section IX.C.1 through IX.C.6 of this ordinance when it can be demonstrated that the information requested is impossible to obtain or it would create a hardship on the applicant to obtain and its absence will not materially affect the review process.

25-57.10 Maintenance and Repair:

- A. **Applicability**
Projects subject to review as in Section I.C of this ordinance shall comply with the requirements of Section X.B and X.C.
- B. **General Maintenance**
1. The design engineer shall prepare a maintenance plan for the stormwater management measures incorporated into the design of a major development.
 2. The maintenance plan shall contain specific preventative maintenance tasks and schedules; cost estimates, including estimated cost of sediment, debris, or trash removal; and the name, address, and telephone number of the person or persons responsible for preventative and corrective maintenance (including replacement). The plan shall contain information on BMP location, design, ownership, maintenance tasks and frequencies, and other details as specified in Chapter 8 of the New Jersey Stormwater Best Management Practices Manual, as well as the tasks specific to the type of BMP, as described in the applicable chapter containing design specifics.
 3. If the maintenance plan identifies a person other than the property owner (for example, a developer, a public agency or homeowners' association) as having the responsibility for maintenance, the plan shall include documentation of such person's or entity's agreement to assume this responsibility, or of the owner's obligation to dedicate a stormwater management facility to such person under an applicable ordinance or regulation.
 4. Responsibility for maintenance shall not be assigned or transferred to the owner or tenant of an individual property in a residential development or project, unless such owner or tenant owns or leases the entire residential development or project. The individual property owner may be

assigned incidental tasks, such as weeding of a green infrastructure BMP, provided the individual agrees to assume these tasks; however, the individual cannot be legally responsible for all of the maintenance required.

5. If the party responsible for maintenance identified under Section X.B.3 above is not a public agency, the maintenance plan and any future revisions based on Section X.B.7 below shall be recorded upon the deed of record for each property on which the maintenance described in the maintenance plan must be undertaken.
 6. Preventative and corrective maintenance shall be performed to maintain the functional parameters (storage volume, infiltration rates, inflow/outflow capacity, etc.) of the stormwater management measure, including, but not limited to, repairs or replacement to the structure; removal of sediment, debris, or trash; restoration of eroded areas; snow and ice removal; fence repair or replacement; restoration of vegetation; and repair or replacement of non-vegetated linings.
 7. The party responsible for maintenance identified under Section X.B.3 above shall perform all of the following requirements:
 - i. maintain a detailed log of all preventative and corrective maintenance for the structural stormwater management measures incorporated into the design of the development, including a record of all inspections and copies of all maintenance-related work orders;
 - ii. evaluate the effectiveness of the maintenance plan at least once per year and adjust the plan and the deed as needed; and
 - iii. retain and make available, upon request by any public entity with administrative, health, environmental, or safety authority over the site, the maintenance plan and the documentation required by Section X.B.6 and B.7 above.
 8. The requirements of Section X.B.3 and B.4 do not apply to stormwater management facilities that are dedicated to and accepted by the municipality or another governmental agency, subject to all applicable municipal stormwater general permit conditions, as issued by the Department.
 9. In the event that the stormwater management facility becomes a danger to public safety or public health, or if it is in need of maintenance or repair, the municipality shall so notify the responsible person in writing. Upon receipt of that notice, the responsible person shall have fourteen (14) days to effect maintenance and repair of the facility in a manner that is approved by the municipal engineer or his designee. The municipality, in its discretion, may extend the time allowed for effecting maintenance and repair for good cause. If the responsible person fails or refuses to perform such maintenance and repair, the municipality or County may immediately proceed to do so and shall bill the cost thereof to the responsible person. Nonpayment of such bill may result in a lien on the property.
- C. Nothing in this subsection shall preclude the municipality in which the major development is located from requiring the posting of a performance or maintenance guarantee in accordance with N.J.S.A. 40:55D-53.

25-57.11 Penalties:

Any person(s) who erects, constructs, alters, repairs, converts, maintains, or uses any building; structure or land in violation of this ordinance shall be subject to the penalties as specified in the Revised General Ordinances of the Borough of Farmingdale, Section 1-5 entitled "General Penalty."

25-57.12 Severability:

Each section, subsection, sentence, clause and phrase of this Ordinance is declared to be an independent section, subsection, sentence, clause and phrase, and the finding or holding of any such portion of this Ordinance to be unconstitutional, void, or ineffective for any cause, or reason, shall not affect any other portion of this Ordinance.

25-57.13 Effective Date:

This Ordinance shall be in full force and effect from and after its adoption and any publication as required by law.

NEW BUSINESS -RESOLUTIONS

RESOLUTION 97-2020

Motion to approve the resolution by C/Steinfeld; seconded by C/Brandl

Roll Call: AYE – C/Linszky, C/Steinfeld, C/Brandl, C/Corallo
ABSENT – C/Dyevoich, C/Sagan

RESOLUTION 97-2020

AUTHORIZING PAYMENT OF THE BILLS

BE IT RESOLVED that the bills as presented to the Finance Committee, all having been certified and approved as complete as to form, goods having been delivered, and/or services performed and sufficient funds being available for payment for said bills in the amount of \$361,334.16; and

BE IT FURTHER RESOLVED that payroll as verified by the Payroll Clerk be remitted for the current pay period.

November 25, 2020

Vendor # Name

PO #	PO Date	Description	Status	Amount	Void Amount	Contract	PO Type
SHAFFER WILLIAM SHAFFER							
	11/18/2020	Christmas Trees	Open	1,872.86	0.00		
000029 VERIZON							
20-00440	11/13/20	FIOS	Open	166.99	0.00		
000063 HERB NEUHAUS							
20-00457	11/20/20	1 Marl Rd session 10/13 & 11/10	Open	80.00	0.00		
000083 Republic Services, Inc.							
20-00441	11/13/20	OCTOBER	Open	451.30	0.00		
000085 VERIZON							
20-00454	11/20/20	11/11 - 12/10	Open	118.52	0.00		
000099 BROADVIEW NETWORKS							

(vv) = Voice Vote (rc) = Roll Call Vote

Visit us at www.farmingdaleborough.org

20-00446	11/13/20	November billing	Open	313.89	0.00
00013 FREEHOLD REG HS DIST					
20-00452	11/20/20	December 2020	Open	51,972.00	0.00
00025 NJ NATURAL GAS					
20-00444	11/13/20	October use	Open	247.11	0.00
00028 VERIZON					
20-00448	11/13/20	November billing	Open	80.92	0.00
00055 ASBURY PARK PRESS					
20-00462	11/20/20	Legal Ad	Open	36.00	0.00
00059 FARMINGDALE-HOWELL 1ST AID					
20-00460	11/20/20	Annual Aid to the 1st Aid	Open	6,000.00	0.00
00076 Manasquan River Regional Sewer					
20-00436	11/04/20	4th quarter billing	Open	89,790.00	0.00
00099 US POSTAL SERVICE					
20-00461	11/20/20	Stamps	Open	550.00	0.00
00117 JERSEY CENTRAL POWER & LIGHT					
20-00455	11/20/20	November billings	Open	3,670.96	0.00
001237 SONNENBLICK, PARKER & SELVERS					
20-00438	11/13/20	MRRSA adv COUNTRYSIDE	Open	332.50	0.00
00186 FARMINGDALE ELEMENTARY SCHOOL					
20-00451	11/20/20	December 2020	Open	174,241.00	0.00
00191 FARMINGDALE FIRE CO.					
20-00458	11/20/20	Reimbursements 2020	Open	8,500.00	0.00
00191 FARMINGDALE FIRE CO. Continued					
20-00459	11/20/20	Yearly Aid to the Fire Departm	Open	<u>10,000.00</u> 18,500.00	0.00
00448 MONMOUTH COUNTY TREAS -					
20-00463	11/23/20	County received 1 day late	Open	17.77	0.00
00449 MONMOUTH COUNTY TREAS -					
20-00464	11/23/20	Health County rec'd 1 day late	Open	0.37	0.00
00450 MONMOUTH COUNTY TREAS -					
20-00465	11/23/20	Library County rec'd 1 day late	Open	1.31	0.00
00451 MONMOUTH COUNTY TREAS -					
20-00466	11/23/20	Open Space 1 day late	Open	2.10	0.00
00746 KEVIN E. KENNEDY, ESQ.					
20-00439	11/13/20	OCTOBER SERVICES	Open	26.00	0.00
00960 POINT BAY FUEL, INC.					
20-00447	11/13/20	Heating Oil	Open	168.57	0.00
00992 MONMOUTH COUNTY S.P.C.A.					
20-00442	11/13/20	ANIMAL CONTROL SERVICES OCT	Open	387.50	0.00
01059 MONMOUTH CTY BOARD OF TAXATION					
20-00435	11/04/20	MOD-IV PROPERTY TAX SYSTEM	Open	500.00	0.00
01376 CANON FINANCIAL SERVICES INC					
20-00453	11/20/20	11/01/20 - 11/30/20	Open	120.19	0.00
01402 SAKOUTIS BROTHERS DISPOSAL, Inc					
20-00450	11/20/20	December 2020	Open	103.87	0.00
01421 NEW JERSEY AMERICAN WATER					
20-00443	11/13/20	OCT BILLING	Open	11,215.50	0.00
01555 DIRECT ENERGY					
20-00445	11/13/20	October use	Open	26.93	0.00
LIZGR005 LIZ GRIFFIN					
20-00456	11/20/20	Certificate webcast	Open	340.00	0.00

Total Purchase Orders: 30 Total P.O. Line Items: 0 Total List Amount: 359,461.30 Total Void Amount: 0.00

Totals by Year-Fund

Fund Description	Fund	Budget Rcvd	Budget Held	Budget Total	Revenue Total	G/L Total	Total
CURRENT OPERATING	0-01	254,079.57	0.00	254,079.57	0.00	0.00	254,079.57
WATER OPERATING F	0-05	13,456.59	0.00	13,456.59	0.00	0.00	13,456.59
SEWER OPERATING F	0-07	<u>90,397.50</u>	<u>0.00</u>	<u>90,397.50</u>	<u>0.00</u>	<u>0.00</u>	<u>90,397.50</u>
Year Total:		357,933.66	0.00	357,933.66	0.00	0.00	357,933.66
CURRENT OPERATING	9-01	3,000.00	0.00	3,000.00	0.00	0.00	3,000.00
Dog (Animal Contr	T-15	387.50	0.00	387.50	0.00	0.00	387.50
Escrows	T-19	<u>13.00</u>	<u>0.00</u>	<u>13.00</u>	<u>0.00</u>	<u>0.00</u>	<u>13.00</u>
Year Total:		<u>400.50</u>	<u>0.00</u>	<u>400.50</u>	<u>0.00</u>	<u>0.00</u>	<u>400.50</u>
Total Of All Funds:		361,334.16	0.00	361,334.16	0.00	0.00	361,334.16

RESOLUTION 98-2020

Motion to approve the resolution by C/Linszky; seconded by C/Brandl

Roll Call: AYE – C/Linszky, C/Steinfeld, C/Brandl, C/Corallo

ABSENT – C/Dyevoich, C/Sagan

RESOLUTION 98-2020**AUTHORIZING A SHARED SERVICES AGREEMENT WITH THE FARMINGDALE BOARD OF EDUCATION FOR SNOW SERVICES**

WHEREAS, the Uniform Shared Services and Consolidation Act, N.J.S.A 40A:65-1 et seq., authorizes a local unit to enter into an agreement with any other local unit to provide or receive any service that each local unit participating in the agreement is empowered to provide or receive within its own jurisdiction; and

WHEREAS, the Borough of Farmingdale (the "Borough") and the Farmingdale Board of Education ("Board of Ed") are desirous of entering into an agreement in order to improve safety and save tax payer money by sharing snow removal and care services (the "Agreement"); and

WHEREAS, pursuant to the Agreement, the Borough shall provide the Board of Education with snow services including treatment, cleaning and plowing, and the Board of Education agrees to pay the Borough \$1,500.00 activation fee and fees for application of mix and cleaning and plowing of roadways or walks; and

WHEREAS, the Borough Council has determined that it is appropriate to authorize the Agreement with the Board of Education. **NOW, THEREFORE, BE IT RESOLVED**, that the Mayor and Council of the Borough of Farmingdale do hereby authorize the Mayor to enter into a Shared Services agreement, in the form on file in the Borough Clerk's Office and incorporated therein, with the Farmingdale Board of Education for the shared use of snow services, as per the terms outlined therein.

Snow Plowing Season 2020-2021

Agreement between the Borough of Farmingdale and the Farmingdale Board of Education

Scope

The purpose of this agreement is to codify the services that the Borough of Farmingdale will provide as a shared service, to be paid for by the Farmingdale Board of Education. The work will include plowing the parking lots, clearing the sidewalks and entryways, and using sand/salt on the parking lots and calcium on the sidewalks.

Determination of Snowfall

*In the event of snow or frozen precipitation/ice that does not accumulate as snowfall, the Business Administrator of the Farmingdale Board of Education and the Head of the Department of Public Works will jointly make a determination about wheatear services are **NOT** needed.*

DETERMINATION must be made allowing for proper availability of staff to handle the occurrence. Experience determinations and activation will be made by the Head of the DPW and when/if necessary by the Mayor/Governing Body, based on the availability of staff and the severity of the occurrence, to be able to complete the task prior to the opening of school, to ensure safety, even if there is no communication by the school administration. Delayed openings will be factored into the decision as to completion of the snow removal time. Communication from the school will be made to notify whether school will be opened, closed, or a delayed opening, and this notification must be made with a 4 hour response time prior to completion time.

NOTE: The Borough pre-treats to allow for easier cleanup, pretreating will be done on school property if done on the roadways in town, and charges for same will be billed accordingly.

One Time Costs

\$1500 Activation and Insurance Fee – to be paid in December

Costs and Terms per each occurrence**Sand/Salt mix on roadways and/or calcium on walks.**

\$250 Cost per application to sand/salt entrances, roads and parking lots

\$150 Cost per application to apply calcium to walks

\$45 Hourly rate per man per hour for spot treating

Clean/Plow snow on roadways or walks

\$350 Cost per application to plow entrances, roads, and parking lots

\$45 Hourly rate per man per hour to clean snow from walks

Timeliness

Services will be provided no later than 7:00 am in the event of overnight weather. If there is a delayed opening, services will be provided no later than 8:30 am.

Locations

The Board of Education will install stakes as/if needed prior to the 1st snowfall and remove stakes after last snowfall.

RESOLUTION 99-2020

Motion to approve the resolution by C/Linszky; seconded by C/Brandl

Roll Call: AYE – C/Linszky, C/Steinfeld, C/Brandl, C/Corallo

ABSENT – C/Dyevoich, C/Sagan

RESOLUTION 99-2020**AUTHORIZING EXECUTION OF A SHARED SERVICES AGREEMENT WITH FREEHOLD TOWNSHIP FOR SIGN MAKING SERVICES AND OTHER PUBLIC WORKS**

WHEREAS, the Township of Freehold and the Borough of Farmingdale are interested in Freehold Township providing sign making services and other Public Works related goods; and,

WHEREAS, this cooperative Agreement would be beneficial to the taxpayers in both municipalities; and,

WHEREAS, Freehold Township and Farmingdale Borough have reached an Agreement detailing specifics of the services to be provided and costs for same.

NOW, THEREFORE, BE IT RESOLVED by the Mayor and Council of the Borough of Farmingdale that said Agreement is hereby authorized to be executed; and

BE IT FURTHER RESOLVED that a copy of the Agreement shall be maintained in the Office of the Borough Clerk upon passage of this Resolution and available for public inspection; and

BE IT FURTHER RESOLVED that, pursuant to NJSA 40A:65-1, a certified copy of the within Resolution shall be forwarded to New Jersey Department of Community Affairs, Division of Local Government Services.

SHARED SERVICES AGREEMENT BETWEEN FREEHOLD TOWNSHIP & FARMINGDALE BOROUGH**SIGN MAKING SERVICES & OTHER PUBLIC WORKS RELATED GOODS AND SERVICES**

THIS SHARED SERVICES AGREEMENT is effective the 1st day of January, 2021 between **TOWNSHIP OF FREEHOLD** a municipal corporation of the State of New Jersey;

and **BOROUGH OF FARMINGDALE**, a municipal corporation of the State of New Jersey;

The purpose of this Agreement is for Freehold Township to provide sign making services and other Public Works related goods and services to Farmingdale Borough according to the following terms:

1. This Agreement shall take effect January 1, 2021 – December 31, 2021
2. Freehold Township shall provide as-needed sign making services and other Public Works related goods and services to the Borough of Farmingdale according to the terms and conditions set forth below.
3. Freehold Township shall charge Farmingdale Borough for the above foods and/or services as follows:
 - a. On an as-needed basis, where a proposal will be provided by Freehold Township for the specified sizes and types of signs and/or other Public Works related goods and services as required by Farmingdale Borough, prior to performing the work.
4. Freehold Township shall provide Farmingdale Borough with itemized monthly billings. Payment shall be due from Farmingdale within 30 (thirty) days of the date of billing.

RESOLUTION 100-2020

Motion to approve the resolution by C/Linszky; seconded by C/Steinfeld

Mr. Whille confirmed they are a huge help.

Roll Call: AYE – C/Linszky, C/Steinfeld, C/Brandl, C/Corallo

ABSENT – C/Dyevoich, C/Sagan

RESOLUTION 100-2020**AUTHORIZING EXECUTION OF A SHARED SERVICES AGREEMENT WITH FREEHOLD TOWNSHIP FOR LICENSED OPERATIONAL SERVICES FOR FARMINGDALE WATER-SEWER UTILITIES**

WHEREAS, the Township of Freehold and the Borough of Farmingdale are interested in Freehold Township providing Licensed Operational Services for Farmingdale Borough Water-Sewer Utilities; and,

WHEREAS, this cooperative Agreement would be beneficial to the taxpayers in both municipalities; and,

WHEREAS, Freehold Township and Farmingdale Borough have reached an Agreement detailing specifics of the services to be provided and costs for same.

NOW, THEREFORE, BE IT RESOLVED by the Mayor and Council of the Borough of Farmingdale that said Agreement is hereby authorized to be executed; and

BE IT FURTHER RESOLVED that a copy of the Agreement shall be maintained in the Office of the Borough Clerk upon passage of this Resolution and available for public inspection; and

BE IT FURTHER RESOLVED that, pursuant to NJSA 40A:65-1, a certified copy of the within Resolution shall be forwarded to New Jersey Department of Community Affairs, Division of Local Government Services.

SHARED SERVICES AGREEMENT BETWEEN FREEHOLD TOWNSHIP & FARMINGDALE BOROUGH LICENSED OPERATIONAL SERVICES FOR FARMINGDALE WATER-SEWER UTILITIES

THIS SHARED SERVICES AGREEMENT is effective the 1st day of January, 2021 between **TOWNSHIP OF FREEHOLD** and **BOROUGH OF FARMINGDALE**, municipal corporations of the State of New Jersey;

The purpose of this Agreement is for Freehold Township to provide Licensed Operational Services for Farmingdale Borough Water-Sewer Utilities to include the following:

1. Conduct weekly site visit to the water treatment plant and wastewater collection system
2. Prepare all required daily, monthly and quarterly reports with the operators
3. Assist in the review of day-to-day operations
4. Computerize State-Reporting requirements
5. Create a computerized operation and maintenance schedule to include daily, weekly and monthly maintenance for the water treatment plant and wastewater collection system
6. Assist in the inspection and construction activities of the treatment plant and water tank
7. Train all operators in the operation of the water treatment facility and wastewater collection system
8. Become the licensed operator for the wastewater C-1 wastewater collection system, T-1 water treatment plant and W-1 water distribution system.
9. Assist in the preparation of operation and maintenance manuals for the public water system and wastewater collection system

In addition, Freehold Township shall provide said services according to the following:

1. This Agreement shall take effect January 1, 2021 and shall expire December 31, 2021. Either municipality may terminate this Agreement by giving 30 days advanced written notice to the other party.
2. The following Freehold Township staff members with associated New Jersey State Operational Licenses will be available under the supervision of Freehold Township for oversight of the Farmingdale Borough's Utility:

Freehold Township Utilities Staff Licenses

Timothy Keune, Superintendent of Water & Sewer	T-3, C-4 & W-4
Christopher Beeh, Assistant Superintendent of Water & Sewer	T-3, C-2 & W-3
James Alexander, Supervisor of Water & Sewer	T-3, C-2 & W-2

Freehold Township reserves the right to substitute personnel for each of the positions, provided any replacement personnel hold the same or superior licensing and hold the same position of responsibility with the Township.

3. Freehold Township further offers equipment, owned and operated by the Freehold Township Utilities Department, for use by the Borough of Farmingdale on a scheduled or as-needed basis or for emergencies. The following equipment is available at the corresponding daily rates:

<u>Freehold Township Equipment</u>	<u>Daily Rate</u>
Sewer jet-vac truck with 2-man crew	\$1,450.00
Closed-circuit television camera truck	\$1,200.00

Freehold Township reserves the right to retire, replace or not to replace any listed equipment.

4. The rate for Operational Services using the above-referenced staff will be \$1,844.85 per month (\$22,138.20 total) and will be billed monthly by the Township.
5. Payment shall be due from Farmingdale Borough within 30 days of the date of billing.
6. During the term of the Agreement and for one year past the expiration of the Agreement, Farmingdale Borough agrees not to employ any person who is a Freehold Township employee, subcontractor or agent who provides Water-Sewer Utilities services to Farmingdale Borough in accordance with this Agreement.
7. It is agreed that no employer/employee relationship will exist between the Freehold Township employees and Farmingdale Borough. Freehold Township agrees to maintain all required insurance on its employees, including workers' compensation insurance

COUNCIL COMMENTS

Mayor Daly noted the tree lighting is this Friday, December 4 at 6:30pm. The tree lighting will be dedicated to the first responders.

10. CLOSED SESSION

Resolution 101-2020

1) Personnel – Professional Appointments

Mayor Daly noted there would be no action taken after closed session.

Motion to approve the resolution by C/Linszky; seconded by C/Brandl

Roll Call: AYE – C/Linszky, C/Steinfeld, C/Brandl, C/Corallo

ABSENT – C/Dyevoich, C/Sagan

RESOLUTION 101-2020

AUTHORIZING EXECUTIVE SESSION UNDER THE OPEN PUBLIC MEETINGS ACT FOR THE MAYOR AND COUNCIL OF THE BOROUGH OF FARMINGDALE

WHEREAS, pursuant to the Open Public Meetings Act, N.J.S.A. 10:4-6 et seq., a municipality may exclude the public from a meeting of the Municipal Council where the Council intends to discuss certain matters for which privacy is needed in order to protect the public interest or certain enumerated private interests; and

WHEREAS, it is necessary for the Mayor and Council of the Borough of Farmingdale to discuss in session not open to the public certain matters that are required by law to be confidential, more specifically:

1) Personnel – Professional Appointments

WHEREAS, it is anticipated that the minutes from the deliberations conducted in closed session may be disclosed to the public upon the determination that the public interest will no longer be served by such confidentiality.

NOW THEREFORE BE IT RESOLVED that the Mayor and Council of the Borough of Farmingdale do hereby authorize the above-referenced executive session to be held closed to the public, on December 1, 2020

Council entered Closed Session at 7:38 pm

Council returned from Closed Session at 8:20 pm

ADJOURNMENT

Council adjourned at 8:20 pm

Motion to adjourn by C/Linszky; seconded by C/Brandl

Voice Vote: AYE – C/Linszky, C/Steinfeld, C/Brandl, C/Corallo

ABSENT – C/Dyevoich, C/Sagan

Respectfully Submitted,



Corinne DiCorcia, RMC, Borough Clerk

Exhibits are on file in the Borough Clerk's office, according to the New Jersey State Records Retention Schedule established by N.J.S.A. 47:3-15 et seq. and approved by the State Records Committee
For Approval: 12/15/2020