



#12 AWG BLUE INSULATED SOLID OR STRANDED COPPER LOCATOR WIRE ON TOP OF ALL NON-FERROUS PIPE. ATTACH WIRE TO PIPE WITH ZIP TIES AT 5' INTERVALS.

**NOTES:**

1. SEE SPECIFICATIONS SECTION 02275, PART 2 – PRODUCTS FOR COMPOSITION OF SELECT EARTH BACKFILL AND COMMON TRENCH BACKFILL.
2. SEE PAVEMENT REPAIR DETAIL FOR PIPE LAID WITHIN AN EXISTING PAVED STREET.
3. TRENCHES REQUIRING SHORING AND BRACING, DIMENSIONS SHALL BE TAKEN FROM THE INSIDE FACE OF THE SHORING AND BRACING.
4. NO ROCKS OR BOULDERS 4" OR LARGER TO BE USED IN BACKFILL.
5. ALL BACKFILL MATERIAL SHALL BE SUITABLE NATIVE MATERIAL.
6. BACKFILL SHALL BE TAMPED IN 6" LIFTS.
7. ACHIEVE 95% COMPACTION IN BACKFILL IN NON-PAVED AREAS AND 100% COMPACTION IN PAVED AREAS.



TITLE: <b>PIPE LAYING CONDITIONS</b> PO BOX 1436 900 S. BECKFORD DRIVE HENDERSON, NC 27536	CITY OF HENDERSON 252-430-5728 (fax) 252-431-0124 www.ci.henderson.nc.us	REV DATE:	DWG NO:
		7/29/15	W.002
		SCALE:	SHEET #:
		NTS	1 OF 1